


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD 15-047-20024-0000

NORTH



Locate well correctly on above
Section Plat

Edwards County, Sec. 13 Twp 26S Rge 19W ~~XEX~~ (W)
Location as "NE/CNW/SW" or footage from lines C NE NW
Lease Owner Glen Rupe
Lease Name Michaelis Well No. 1
Office Address 222 Brown Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-8-68 19
Application for plugging filed 3-8-68 19
Application for plugging approved 3-8-68 19
Plugging commenced 3-8-68 19
Plugging completed 3-8-68 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	290'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 270' - plug - 25 sks. cement through drill pipe
Mud to 40' - plug - 1/2 sk. hulls, 10 sks. cement
2 sks. in rathole

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
Box 486, Great Bend, Kansas 67530
(Address)

Subscribed and Sworn to before me this 11th day of March 1968

My commission expires April 1, 1968
Glenda [Signature]
Notary Public.

15-047-20624-0000

DRILLER'S LOG

COMPANY: Glen Rupe
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: MICHAELIS #1
 LOCATION: C NE NW SECTION 13-26S-19W
 EDWARDS COUNTY, KANSAS
 COMMENCED: 2-23-68
 COMPLETED: 3-8-68

0	292	Sand, Shale
292	710	Shale, Redbed
710	722	Anhydrite
722	1100	Anhydrite
1100	1290	Redbed, Shale
1290	1330	Anhydrite
1330	1575	Redbed, Shale, Shells
1575	2107	Shale, Sand, Shells
2107	2260	Shale
2260	2380	Lime, Shale
2380	2525	Shale, Lime
2525	2645	Lime, Shale
2645	2767	Lime
2767	2835	Lime, Shale
2835	3130	Lime
3130	3310	Shale, Lime
3310	3410	Lime, Shale
3410	3541	Shale, Lime
3541	3815	Lime, Shale
3815	3940	Shale, Lime
3940	4105	Lime
4105	4678	Lime
4678	4696	Lime, Shale
4696	4725	Lime
4725	4803	Chert, Lime
4803	4850	Sand, Lime
	<u>4850</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 12 1968
 CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" new 20# surface casing set @ 290' cemented with 250 sacks
 Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Michaelis #1 Well, located C NE NW of Section 13, Township 26 South, Range 19 West, Edwards County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 11th day of March, 1968.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1971