


15-047-00056-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Edwards County, Sec. 15 Twp. 26S Rge. 19 (X) (W)
Location as "NE/CNW/SE/SW" or footage from lines. NE NE NE
Lease Owner. Natural Gas & Oil Co.
Lease Name Craft Well No. 1
Office Address. Box 105, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-25 1957
Application for plugging filed 2-25 1957
Application for plugging approved 2-25 1957
Plugging commenced 1:00 A.M. 2-26 1957
Plugging completed 2:00 A.M. 2-26 1957
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes-telephone

Name of Conservation Agent who supervised plugging of this well Mr. Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8-5/8 | 432' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 300'. Set Plug with 1/3 sack hulls. Mixed 20 sacks cement by hand and put in thru drill pipe.
Filled hole with heavy rotary mud to 35'. Set plug with 1/3 sack hulls. Mixed 10 sacks cement by hand and put in thru drill pipe. Cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Honaker-Davis Drlg. Co.
Address 2008 Lakin, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
J. B. Steele, Jr. (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Steele, Jr.
P. O. Box 105, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of February, 1957

Richard R. Krick
Notary Public.
STATE CORPORATION COMMISSION

My commission expires July 29, 1959

PLUGGING
FILE, SEC. 15 T. 26 R. 19W
BOOK PAGE 144 LINE 23

FEB 28 1957 2-28-1957
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

15-047-00056-0000

Craft No. 1
Loc: NE NE NE
Sec: 15-26S-19W
Edwards County, Kansas
Company: Natural Gas & Oil Co.
Contractor: Honaker-Davis Drlg. Co.

Comm: 2- 5-57
Comp: 2-26-57
Rotary Total Depth: 5155'
Casing: 8-5/8" at 432'
D & A

| | | |
|------|------|------------------------|
| 0 | 200 | Sand |
| 200 | 275 | Sandy Clay |
| 275 | 580 | Blue Shale |
| 580 | 700 | Red Bed |
| 700 | 725 | Anhydrite |
| 725 | 1050 | Red Bed |
| 1050 | 1275 | Red Bed & Salt |
| 1275 | 1320 | Gyp |
| 1320 | 1435 | Red Bed, Lime & Shells |
| 1435 | 1485 | Red Bed & Black Shale |
| 1485 | 2020 | Red Bed & Shale |
| 2020 | 2140 | Blud Shale & Shells |
| 2140 | 2290 | Shale & Lime |
| 2290 | 3350 | Lime & Shale |
| 3350 | 3475 | Shale & Lime |
| 3475 | 4320 | Lime & Shale |
| 4320 | 4370 | Lime |
| 4370 | 4478 | Lime & Shale |
| 4478 | 4515 | Lime |
| 4515 | 4599 | Lime, Shale & Chert |
| 4599 | 4695 | Lime & Shale |
| 4695 | 4724 | Lime, Shale & Chert |
| 4724 | 4745 | Lime & Chert |
| 4745 | 4765 | Chert & Shale |
| 4765 | 4772 | Chert, Shale & Lime |
| 4772 | 4785 | Lime & Shale |
| 4785 | 4914 | Lime, Shale & Chert |
| 4914 | 4993 | Chert & Lime |
| 4993 | 5000 | Lime & Chert |
| 5000 | 5076 | Chert & Lime |
| 5076 | 5155 | Shale & Lime |
| 5155 | | Total Rotary Depth |

8-5/8" casing cemented at 432' with 400 sacks cement and 2% calcium chloride.

RECORDED
STATE OF KANSAS
DIVISION
D & A
Edwards County, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

H. S. Forbes
H. S. Forbes

Subscribed and sworn to before me this 26th day of February, 1957.

Kenneth G. Fischer
Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

PLUGGING
FILED SEC. 15 T. 26 R. 19W
BOOK PAGE 144 LINE 23