

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Edwards County. Sec. 26 Twp. 26S Rge. 19 (~~EX~~) (W)

Location as "NE/CNW/SW" or footage from lines C SE SE

Lease Owner Pickrell Drilling Company

Lease Name King "B" Well No. 1

Office Address 705 Fourth National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 16, 1960

Application for plugging filed September 16, 1960

Application for plugging approved September 16, 1960

Plugging commenced September 16, 1960

Plugging completed September 16, 1960

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, 222 S. Main, St. John, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4917 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	320'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with heavy mud to 310', set plug and cement with 20 sks. Fill with heavy mud to 35', set plug and cement with 10 sks cement.
Plug rat hole with 2 sks cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company

Address 705 Fourth National Bank Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

C. W. Sebts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebts

(Address) _____

SUBSCRIBED AND SWORN to before me this 20th day of September, 1960

Marilyn A. Davis
Marilyn A. Davis Notary Public.

My commission expires March 7, 1964

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Bldg.
 Wichita, Kansas

LOCATION: C SE SE Sec. 26, Twp. 26S, Rge. 19W,
 Edwards County, Kansas

Rotary Drilling Commenced 8-29-60
 Rotary Drilling Completed 9-16-60

15-047-60729-0000

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: 320' 8 5/8" 17.3# Armco Spiralweld csg. cemented w/225 sks., circ.
 No oil string, D & A

KING "B" #1
LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

150	Sand	
330	Blue shale	
530	Shale	<u>Circulate for Samples</u>
700	Red-bed	4715
715	Blaine	4748
965	Shale, shells	4755
1165	Shells, sand, shale	4760
1275	Sandy shale	4765
1310	Anhydrite	4795
1970	Shale, shells	4810
2325	Lime, shale	4830
2455	Shale, lime	4851
2595	Lime, shale	
3078	Lime	<u>Slope Test</u>
3180	Lime, shale	2500-0°
3240	Lime	3145-0°
3650	Lime, shale	4500-0°
3765	Lime	
4360	Lime, shale	<u>S.L.M.</u>
4655	Lime	
4689	Lime, shale	2000.00 OK
4717	Lime	3500.00 OK
4746	Lime, sand	4273.41 OK
4917	Miss., T.D.	4274.72 OK

RECEIVED
 STATE CORPORATE COMMISSION
 SEP 21 1960
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By *C. W. Sebitts*
 Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.

On this 20th day of September, 1960, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: March 7, 1964

Marilyn A. Davis
 Notary Public
 Marilyn A. Davis