

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

X			

Locate well correctly on above
Section Plat

Edwards County, Sec. 35 Twp. 26S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines C-SW-SW
Lease Owner Sunray DX Oil Company
Lease Name Gus Edwards Well No. 1
Office Address 321 West Douglas, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 4-28- 19 62
Application for plugging filed 4-17- 19 63
Application for plugging approved 4-18- 19 63
Plugging commenced 4-19- 19 63
Plugging completed 4-19- 19 63
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production April 8, 19 63
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Box 652, Pratt, Kansas
Producing formation Lsg. Kansas City Depth to top 4194 Bottom 4215 Total Depth of Well 5012 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lsg. Kansas City	Oil	4194	4215	8 5/8"	329'	0'
Mississippi	Water	4776	5012	5 1/2"	5004'	2541'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Filled hole with mud from total depth to 4215' and sanded to 4219'. Set 5 sacks of cement at 4219'. Filled with mud to 225' and set 10' rock bridge and 20 sacks of cement. Filled with mud to 40' and set 10' rock bridge and 10 sacks of cement to surface. Well plugged and abandoned.

RECEIVED
STATE CORPORATION COMMISSION

APR 23 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company
Address P. O. Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Gary W. Pierce (employee of owner) or (owner/lessee) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary W. Pierce
321 West Douglas, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of April, 19 63

My commission expires July 13, 1963

Notary Public.

15-047-00253-0000

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
April 24, 1962

Contractor: Stickle Drilling Company
Date Commenced: April 4, 1962
Date Completed: April 21, 1962

Gus Edwards Well No. 1
Ctr. SW SW Sec. 35-26S-19W
Edwards County, Kansas

DRILLER'S LOG

Depth Figures Indicate Base of Formation:

Surface clay and sand	225
Red bed and shells	330
Red bed	1272
Anhydrite	1310
Shale and shells	1695
Shale and sand	2165
Shale	2280
Lime and shale	2555
Shale	2590
Lime	2705
Lime and shale	2855
Lime	2948
Lime and shale	3240
Shale	3385
Shale and lime	3540
Shale, chalk and lime	3659
Lime	3765
Lime and shale	3898
Sandy lime and shale	4022
Lime and shale	4120
Lime	4708
Lime and shale	4754
Lime	4763
Lime and shale	4775
Chert and lime	4790
Lime and chat lime	4810
Chert and lime	4862
Shale w/sandy lime streaks	4925
Shale and lime	4944
Lime and chert	4948
Lime	5012 TD

STATE DEPARTMENT OF
STATE GEOLOGICAL SURVEY

APR 18 1963

CONSERVATION DIVISION
Wichita, Kansas

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray Mid-Continent Oil Company's Gus Edwards Well No. 1, Center of SW/4 of SW/4 of Section 35-26S-19W., Edwards County, Kansas.


FRED E. STICKLE

Notary Public

My Commission expires March 24, 1962.