

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

15-055-10071-00-01

API NUMBER N/A (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Helmreich & Payne, Inc. OPERATOR'S LICENSE NO. 5293 6-92

ADDRESS P.O. Box 558 Garden City, KS PHONE # (316) 276-3693

LEASE (FARM) PPU WELL NO. 49 WELL LOCATION 330' N/C/SW COUNTY FI

SEC. 32 TWP. 26^S RGE. 34 (E) or (W) TOTAL DEPTH 5209 PLUG BACK TD 5171

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL X DOCKET NO.

SURFACE CASING SIZE 8-5/8 SET AT 823 CEMENTED WITH 450 SACKS

CASING SIZE 5 1/2 SET AT 5209 CEMENTED WITH 400 SACKS

PERFORATED AT Miss 5092-5100 Cmt. top stage w/ 250 sks

CONDITION OF WELL: GOOD POOR X CASING LEAK X JUNK IN HOLE

PROPOSED METHOD OF PLUGGING per Richard Lacey, KSCC. Pump 150 sks Class C w/ 3% CaCl₂.

Displace to 2000: Let set up. Perf bottom of surface @ 810: Circ 175 sks 65/35 poz to surface.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED?
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon application approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

James Ford James Ford PHONE # (316) 276-3693

ADDRESS P.O. Box 558 Garden City, KS 67846

PLUGGING CONTRACTOR Dowell LICENSE NO.

ADDRESS Ulysses, Kansas PHONE # (316) 356-1272

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED:

Ken Grellik
(Operator or Agent)

FORM NO. 1 (REVISED IN 1947) (12-13-50)

SCHLUMBERGER WELL SURVEYING CORPORATION
HOUSTON, TEXAS



Sonic Log

COUNTY FINNEY FIELD or LOCATION PLEASANT PRAIRIE LOCATION SEC. 32-265-34W WELL JONES 10" 34	COMPANY HELMERICH & PAYNE INC.	Other Surveys I-ES
	WELL PPU W/49 JONES 10" 34	Location of Well 590' FR S/L & 1980' FR E/L
	FIELD PLEASANT PRAIRIE	
	LOCATION SEC. 32-265-34W	
COMPANY HELMERICH & PAYNE INC.	COUNTY FINNEY	Elevation: K.B.: 2997
	STATE KANSAS	D.F.: 2995 or G.L.: 2985

Log Depths Measured From K.B. 12 Ft. above G.L.

RUN No.	ONE		
Date	12-8-59		
First Reading	5206		
Last Reading	3400		
Feet Measured	1806		
Csg. Schlum.			
Csg. Driller	823		
Depth Reached	5210		
Bottom Driller	5215		
Mud Nat.	CHEMICAL		
Dens. Visc.	9.8 55		
Mud Resist.	2.02 @ 55 °F	@ °F	@ °F
" Res. BHT	.95 @ 118 °F	@ °F	@ °F
" pH	8.5 @ °F	@ °F	@ °F
" Wtr. Loss	6.4 CC 30 min	CC 30 min	CC 30 min
" Rmf M	.65 @ 118 °F	@ °F	@ °F
Bit Size	7 7/8"		
Span:	1. 5215 To 3400	To	To
	To	To	To
Opr. Rig Time	3 HOURS		
Truck No.	2509-LIBERAL		
Recorded By	ROSS		
Witness	NELSON		

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1962

REMARKS VIC No.: B-135
 VIS No.: D-110
 GR. CAL.: B-68-455-100-400
 SOLD HERE

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

March 19, 1992

Helmerich & Payne Inc
Box 558
Garden City KS 67846

PPU 49
330' N C SW
Sec. 32-26-34W
Finney County

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760