

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION

8-31-81

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15- 05520184-000
Wichita, Kansas

Operator's Full Name Winfield Resources Corporation
Complete Address PO Box 880, Parker, Colo, 80134
Lease Name Cisco Dome Oil & Gas Corp Well No. 1
Location C. NW. SW. NE Sec. 19 Twp. 26 Rge. 34 (East) (West)
County Linney Total Depth 4540
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated

Plugging Contractor Lakin Drilling
Address Lakin Kans License No.
Operation Completed: Hour: 1:15 AM Day: 27 Month: Aug Year: 1981
Plugging Operations attended by Agent? All Part X None

The above well was plugged as follows:

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1981
CONSERVATION DIVISION
Wichita, Kansas

There was 816' of 8 1/2" surface casing, c.c.
with 350. Halliburton light + 150 lbs class
H. Cement. Filled with mud to 3100 1st
plug at 3100-2500' with 140 lbs to cover
gas zones. Filled with mud to 800' pushed
rubber plug to 800'. 2nd plug at 800' with
40 lbs cement. Filled with mud to 40' built
solid bridge. 3rd plug at 40' with 10 lbs
cement. 5' skin set hole accomplished

I hereby certify that the above well was plugged as herein stated.

by Haliburton
Perryton
NOICED
DATE 9-29-81
INV. NO. 7738-W

Signed: Phenex Thomas
Conservation Division Agent