

SEP 15 1982

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

CONSERVATION DIVISION
Wichita, Kansas

API Number 15-~~594~~-655-10016-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Champion Petroleum Co.

Complete Address 6441 NW Grand Blvd. Atchison Towers W Suite 300
OKLA CITY, OK. 73116

Lease Name Reeve Well No. #1

Location C SW-NE Sec. 7 Twp. 26 Rge. 34 (East)(West)

County FINNEY Total Depth 5171

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Champion Petroleum

Address SAME License No. _____

Operation Completed: Hour: 6:30 PM Day: 9 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

10 3/4" S.P. to 861' w/ 360 sx riv. 7" to 5173 w/ 300 sx

Staged @ 3156' w/ 400 sx top cement @ 2100' Staged @ 1878'

w/ 300 sx - cement @ 900' Perf. 5123 to 4888'

Run gauge ring & Basket to 4838' - Set Cast iron

Bridge Plug @ 4800' by Rosel Well Perforators

Set C.I.B.P. @ 1146' Pump 150 sx cement from

1146' to surface - Pump 25 sx in annulus w/ 700 #

almost Eric to top of casing. Cement by Halliburton

Amount of Surface Casing: 10 3/4" to 861

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Steve Dumont
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED
DATE: 9-23-82
INV. NO. 1166-u

CHAMPLIN OIL & REFINING CO.
 C. LEE REEVE #1
 C SW NE 7-26S-34W,
 FINNEY COUNTY,
 KANSAS

15-055-10616-0000

- 0 - 332 Sand & Surface Shale
- 332 - 860 Sand & Surface Shale
- 860 - 1255 Sand & Clay
- 1255 - 2035 Sand, Shale & Lime Streaks
- 2035 - 2275 Gyp, Shale & Lime
- 2275 - 2450 Lime & Shale
- 2450 - 2565 Lime
- 2565 - 2712 Lime, Shale & Chalk
- 2712 - 5172 Lime
- 5172 - TD

PRODUCTION
 HAS COMMENCED
 CASING AHEAD
 HAS COMPLETED
 WELL TOGETHER WITH

Champlin Oil & Refining Co.

STATE OF Kansas COUNTY OF Barton,
 J. W. Meyers (EMPLOYEE OF OWNER) of the above described
 well, being first duly sworn on oath, says:

That I have knowledge of the facts, statements, and matters herein
 contained and the log of the above-described well as filed and that
 the same are true and correct. So help me God.

(Signature) *J. W. Meyers*
 Box 167, Ellinwood, Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 18 1962
 CONSERVATION DIVISION
 Wichita, Kansas

Subscribed and Sworn to before me this 23 day of November 1959
W. Kenneth Stearns
 Notary Public

My commission expires 5-22-62