

15-083-00167-0000

Form GP-3  
Rev. 6-26-62

10 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 4 1962

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Wilcox Oil Company

Complete Address: Box 1440 Tulsa, Okla.

Lease Name Nall Well No. # 1

Location C SW SE Sec. 1 Twp. 24S Rge. (E) (W) 23

County Hodgeman Total Depth 4748'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 4:30PM Day 2 Month 12 Year 62

The Above well was plugged as follows: .

8 5/8" 278' Circulated w/cement. 4 1/2" 4748' Cemented.

Top of perforations 4594' to 4748'

Plug bottom w/sand 4748' to 4580' 5 sax.cement 4580' to 4520'

Mud 4520' to 275' Plug and 35 sax.cement 275' to 175'

Mud 175' to 50' 10' Rock bridge 50' to 40'

15 sax.cement 40' to Surface. (Company Pump.)

(Pulled 2502' 4 1/2" Pipe.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 12/6/62

INV. NO. 6162-u