

15-083-20317-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

6-20-74

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Jack Bowles

Complete Address 401 Local Federal Bldg., Oklahoma City, Oklahoma 73102

Lease Name Ryan Well No. 3

Location C SW NE Sec. 25 Twp. 24 Rge. 23 (E) (W)

County Hodgeman Total Depth 4880'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 4:00PM Day 17 Month 6 Year 1974

The above well was plugged as follows:

8 5/8" to 365' circulated w/ cement. 5 1/2" to 4874' cemented.

Top perforations 4651' Plug bottom w/ sand & 5 sacks cement.

Top of 4600' Mud 4600' to 800'

Spotted 80 sacks cement 800' to 500' Mud 500' to 365'

Spotted 30 sacks cement 365' to 265' Mud 265' to 40'

Plug, Halls & 19 sacks cement 40' to 0'. Allied Pump Truck

Pulled 2703' of 5 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 6/21/74
INV NO. 9334-W

Signed: [Signature]
Well Plugging Supervisor