

~~NO~~ KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 14 1964
1-14-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Jones-Gebert Oil Inc.

Complete Address: 205 Central Bldg. Wichita, Kansas

Lease Name Herman Well No. 1

Location C NW NW Sec. 12 Twp. 24 Rge. (E) (W) 23

County Hodgeman Total Depth 4816'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Jones-Gebert Oil Inc.

Address: Wichita, Kansas License No.

Operation Completed: Hour 1030PM Day 12 Month 1 Year 64

The Above well was plugged as follows:

8 5/8"-335' Circulated w/cement.

Mud 4816' to 600' 25 Sax.cement spotted 600' to 525'

Mud 525' to 325' 25 Sax.cement spotted 325' to 250'

Mud 250' to 40' Plug,Hulls,10 Sax.cement 40' to 0

Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 1/14/64
INV. NO. 8449-W