

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
-130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-21,382-0000 (Identifier number of this well). This must be listed for wells drilled since 1957; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company L.L.C. KCC LICENSE # 5056 6/97

ADDRESS 6427 E. Kellogg P.O. Box 780167 (owner/company name) CITY Wichita (operator's)

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE CROSS 'A' WELL# 2-18 SEC. 18 T. 24 R. 17W (East/West)

SW . SW . NW SPOT LOCATION/0000 COUNTY Edwards

2970' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

4950' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

CHECK ONE: OIL WELL X GAS WELL _____ D&A _____ SWD/ENHR WELL _____ DOCKET# _____

CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 360' CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 4422' CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: OPEN HOLE 4422-40 Mississippi

ELEVATION 2138 KB T.D. 4440' PSTD None ANHYDRITE DEPTH 1174 (+964)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, Cement and Halliburton Plug.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACC-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Thom Pool PHONE# (316) 995-3171

ADDRESS P.O. Box 158 City/State Belpre, KS 67519

PLUGGING CONTRACTOR Pratt Well Service KCC LICENSE # 5893 6/97

ADDRESS P.O. Box 847 Pratt, KS 67124 (company name) PHONE # (316) 672-2531 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not Known

PAYMENT OF THE PLUGGING FEE (K.S.A. 52-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 10/8/96 AUTHORIZED OPERATOR/AGENT: Robert E. Panake
(signature)

CROSS "A" 2-18

18-24-17w



ATLAS WIRELINE SERVICES

COMPENSATED Z-DENSILOG GAMMA RAY

COMPENSATED NEUTRON

FILE NO.	COMPANY <u>F. G. HOLL COMPANY</u>	
RPI NO.	WELL <u>CROSS "A" 2-18</u>	
<u>15-047-21382</u>	FIELD <u>WAC</u>	
<u>Tops + Tests</u>	COUNTY <u>EDWARDS</u>	STATE <u>KANSAS</u>
FINAL PRINT	LOCATION: SW SW NW	OTHER SERVICES DIFL/GR/SP SEE REMARKS
<u>FGH-Geol. File</u>	SEC <u>18</u> TWP <u>24S</u> RGE <u>17W</u>	
PERMANENT DATUM <u>GROUND LEVEL</u>	ELEV. <u>2129</u>	ELEVATIONS
LOGGING MEASURED FROM <u>K.B.</u>	<u>9</u> FT. ABOVE P.D.	KB 2138
DRILLING MEASURED FROM <u>KELLY BUSHING</u>		DF
		GL 2129
DATE	<u>11-JULY-91</u>	
RUN	<u>1</u>	
SERVICE ORDER	<u>84574</u>	
DEPTH-DRILLER	<u>4440</u>	
DEPTH-LOGGER	<u>4436</u>	
BOTTOM LOGGED INTERVAL	<u>4434</u>	
TOP LOGGED INTERVAL	<u>3300</u>	
CASING - DRILLER	<u>8 5/8</u>	@ <u>360</u>
CASING - LOGGER	<u>362</u>	
BIT SIZE	<u>7 7/8</u>	
TYPE FLUID IN HOLE	<u>PREMIX-MONPAC</u>	
DENSITY / VISCOSITY	<u>9.4</u>	<u>62</u>
PH / FLUID LOSS	<u>9.5</u>	<u>11.6</u>
SOURCE OF SAMPLE	<u>FLOWLINE</u>	
RM AT MEAS. TEMP.	<u>.263</u>	@ <u>90</u>
RMF AT MEAS. TEMP.	<u>.199</u>	@ <u>90</u>
RMC AT MEAS. TEMP.	<u>.321</u>	@ <u>90</u>
SOURCE OF RMF / RMC	<u>M</u>	<u>M</u>
RM AT BHT	<u>.201</u>	@ <u>118</u>
TIME SINCE CIRCULATION	<u>4 HRS.</u>	
MAX. REC. TEMP. DEG. F	<u>118</u>	
EQUIP. NO. / LOC.	<u>HL 6355</u>	<u>GREAT BEND</u>
RECORDED BY	<u>DIRK BECKER</u>	
WITNESSED BY	<u>W.B. BIDLEMAN/A. MERRICK</u>	

10-10-96

1991 OCT 10 10 26
KANSAS GEOLOGICAL SURVEY
RECEIVED

CROSS 'A' 2-18

18-24-17W

15-047-21382

DRILLING TIME
AND
SAMPLE LOG

F6H-Geol. File

COMPANY F.G. HOLL COMPANY
LEASE CROSS 'A' WELL NO. 2-18
FIELD _____
LOCATION SW SW NW
SECTION 18 TOWNSHIP 24s RANGE 17w
COUNTY EDWARDS STATE KANSAS

ELEVATIONS
KB 2138 FEET
DF _____ FEET
GL 2129 FEET
MEASUREMENTS ARE ALL
FROM K.B.

CONTRACTOR STERLING DRILLING RIG NO. 4
COMMENCED DRILLING JULY 1, 1991
COMPLETED DRILLING JULY 11, 1991
RTD 4440 FEET LTD 4436 FEET
MUD UP AT 3375 FEET MUD TYPE MONPAC

CASING
8 7/8" @ 360' KB w/250 sx.
5 1/2" @ 4422' KB w/225 sx.

ELECTRICAL SURVEYS
WESTERN ATLAS
ZDLC/CN/DIFL/GR/
SP/Cal.

SAMPLES SAVED FROM 2300 FEET TO 4440 FEET
DRILLING TIME KEPT FROM 2300 FEET TO 4440 FEET
SAMPLES EXAMINED FROM 3400 FEET TO 4440 FEET
GEOLOGICAL SUPERVISION FROM 3475 FEET TO 4440 FEET
GEOLOGIST W. BRYCE BIDDLEMAN

DRILL STEM TESTING BY SUPERIOR TESTERS (2)
GAS DETECTOR BLUE JAY LOGGING

Hotwire 3 Chromatograph in service from 2400.

1990 OCT 0 FILE 26
KANSAS STATE UNIVERSITY
GEOLOGICAL ENGINEERING
DEPARTMENT



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

October 10, 1996

F G Holl Company LLC
6427 E Kellogg P O Box 780167
Wichita KS 67278-0167

Cross 'A' #2-18
API 15-047-21,382
2970 FSL 4950 FEL
Sec. 18-24S-17W
Edwards County

Dear Thom Pool,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760