

8-10

RECEIVED
KANSAS CORPORATION COMMISSION

2-070569

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

AUG 15 1995
8-15-95
CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-155-21,350 - 0000
W/2, W/2, NW, SECTION 06 TOWNSHIP 25 RANGE 08W

OPERATOR LICENSE # 6170

3960 FEET FROM S SECTION LINE
4950 FEET FROM E SECTION LINE

OPERATOR GLOBE OPERATING, INC.
NAME & P.O. BOX 12
ADDRESS GREAT BEND, KS 67550

LEASE NAME: HARTZELL - TREMBLEY #1

COUNTY: RN 130.00
WELL TOTAL DEPTH: 4000

PIPE: 5 1/2' @ 3990'

SURFACE CASING: 8 5/8" @ 206'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____
PLUGGING CONTRACTOR: MIKES TESTING & SALVAGE
ADDRESS: BOX 209, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 10 MONTH: 8 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO
COMPANY NAME: GLOBE OPERATING, INC. PHONE: _____
WERE: SAND TO 3900' 5 SXS., 35 SXS. @ 1350', 35 SXS. @ 775',
10 SXS. RAT HOLE. 250' TO SURFACE.


PLUGGING PROPOSAL RECEIVED BY: _____
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 2:00 DAY: 10 MONTH: 8 YEAR: 1995

ACTUAL PLUGGING REPORT:
SAND BACK TO 3900' & 5 SXS. OF COMMON SHOT 5 1/2"
CASING OFF @ 3027.' PULLED TO 1350' PUMPED 35 SXS.
PULLED TO 775' PUMPED 35 SXS. PULLED TO 250' CIRCULATED
CMT. TO SURFACE. RAN 1" PIPE IN RAT HOLE PUMPED 10 SXS.

REMARKS: ALLIED #2057 60/40 4% GEL.

I DIDNOT OBSERVE THIS PLUGGING.


Jack Luthi (AGENT)

INVOICED

DATE 8-24-95

INV. NO. 43362

FORM CP-2/3
REV. 3/90