

7-9

2-010006

103  
R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-155-21,205 - 0000

C SW SW, SECTION 10 TOWNSHIP 25 RANGE 8W

OPERATOR LICENSE # 30217

660 FEET FROM S SECTION LINE  
4620 FEET FROM E SECTION LINE

OPERATOR Robba Exploration, Inc.  
NAME & 230 N. Market  
ADDRESS Wichita, KS 67202

LEASE NAME: Locke #1-10  
COUNTY: Reno  
WELL TOTAL DEPTH: 4050' 131.62

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 222'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A X

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Norseman Drilling Co.  
ADDRESS: 200 East 1st, #307, Wichita, KS 67202 LICENSE: 3779

COMPANY TO PLUG AT: HOUR: 1:00a DAY: 9 MONTH: 7 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Jim Riley  
COMPANY NAME: Norseman Drilling PHONE: 316-265-9408

WERE: Fill hole with heavy mud and spot cmt through drill  
pipe - spot 35 sx cmt @ 1125' - spot 35 sx cmt @ 775' -  
spot 35 sx cmt @ 275' - spot 25 sx cmt @ 60' - 15 sx  
in rat hole - 10 sx in mouse hole.

PLUGGING PROPOSAL RECEIVED BY: Doug Louis

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (        ) PART (        ) NONE ( X )

COMPLETED: HOUR: 2:45a DAY: 9 MONTH: 7 YEAR: 1992

ACTUAL PLUGGING REPORT:

Filled hole w/heavy mud and sptd cmt through dp - 35  
sx @ 1125' - 35 sx @ 775' - 35 sx @ 275' - 25 sx @ 60'  
- 10 sx in rat hole - 10 sx in mouse hole. Used 60/40  
poz w/4% gel

RECEIVED  
KANSAS CORPORATION COMMISSION

REMARKS: B. J. Services - invoice # 71798

JUL 24 1992  
7-24-92  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 7-29-92

INV. NO. 35830

*fs/*

Mike Wilson

(AGENT)