

To: 1 090794 3-26
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 057-20,097-0000
NE NW SE, SEC. 26, T 27 S, R 24 WXX
2320 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5817

Lease Name Barngrover Well # 3-26

Operator: Benson Mineral Group, Inc.
Name &
Address 1560 Broadway, Ste. 1900
Denver, CO 80202

County Ford 169.78

Well Total Depth 5224 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 526

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Benson Mineral Group, Inc. License Number 5817

Address 1560 Broadway, Ste. 1900, Denver, CO 80202

Company to plug at: Hour: 3 p.m. Day: 26 Month: 3 Year: 19 97

Plugging proposal received from Phil Kempton

(company name) Benson Mineral Group, Inc. (phone) 303-863-3541

was: 5 1/2" at 2897' w/300 sx cement PBSD 2849', Perfs at 2670-82'

1st plug pump 25 sx cement and 2 sx hulls on bottom,

2nd plug run tubing to 1000' and circulate cement to surface,

3rd plug pump 75 sx cement down backside.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 26 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug ran tubing to 2675' and spotted 35 sx cement and 2 sx hulls,

2nd plug pulled to 1600' and circulated 175 sx cement to surface,

3rd plug hooked onto backside and pumped in 22 sx cement. Shut in pressure 350 psi.

Remarks: Used common cement by BMG. No casing recovery.
(If additional description is necessary, use BACK of this form.)

~~Observe this plugging.~~

Signed [Signature]
(TECHNICIAN)

DATE 4-2-97

INV. NO. 47841

3-28-97

RECEIVED
TRANS. DIV.
APR 23 1997