

To: 1 051420
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-22 15-093-00007-00-01 227R
API NUMBER 19-Drilled 9/57

NE NE SW, SEC. 14, T. 26 S, R. 35 W/E
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5293
Operator: Helmerich & Payne, Inc.
Name & Address P.O. Box 558
Garden City, KS 67846

Lease Name USAB Well # 1-14
County Kearny 168.57
Well Total Depth 5187 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 852

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Dowell License Number _____
Address Ulysses, KS

Company to plug at: Hour: 8:30 a.m. Day: 22 Month: 3 Year: 19 91

Plugging proposal received from James Ford
(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

Perfs: 5 1/2" at 5187' w/800 sx cement, 5 1/2" cement from 2797-2290', Perfs at 4128-4131'

- 1st plug squeeze perfs with 20 sx cement,
- 2nd plug at 1857' with 15 sx cement,
- 3rd plug at 993' with 20 sx cement,
- 4th plug at 40' with 5 sx cement, 5th plug pump 200 sx cement down annulus.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 22 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug perfs squeezed with 20 sx cement,

Pumped the following plugs through tubing: RECEIVED
STATE CORPORATION COMMISSION

- 2nd plug at 1857' with 15 sx cement,
- 3rd plug at 993' with 20 sx cement,
- 4th plug at 40' with 5 sx cement.

5th plug pumped down 10 3/4" X 5 1/2" annulus with 1 sx hulls and 200 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED (check box) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN) RL

DATE 4-9-91

INV. NO. 31409