

1 060812

15-083-10039-00-00

API NUMBER 15-083-Comp. 1-23-64

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SW SE, SEC. 4, T 24 S, R 21 W/EX

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Gleason Well # 1

Operator: Kelso Casing Pulling bought  
Name & Address from Coastal Oil & Gas  
P. O. Box 347  
Chase, KS 67524

County Hodgeman 152.10  
Well Total Depth 4680 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:15 am Day: 24 Month: February Year: 19 86

Plugging proposal received from Vernon Duntz

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4668' PBTD 4680' Open Hole from 4668-4680'

1st plug sand back to 4615' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:30 am Day: 24 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4615' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 200 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Inspector observe this plugging.

DATE 12860  
INV. NO. 12860

Signed Paul A. Luthi (TECHNICIAN)

MAR 4 1986  
3-4-86  
CONSERVATION DIVISION  
Wichita, Kansas