

1091074

TO: STATE CORPORATION COMMISSION API NUMBER 15-055-21,690 - 0000
10'S 150' W W/2 SE SE SEC. 34, T 26 S, R 34 W

CONSERVATION DIVISION - PLUGGING SECTION 650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1140 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MARY JONES WELL # 3

TECHNICIAN'S PLUGGING REPORT COUNTY FINNEY 173.88

OPERATOR LICENSE # 5293 8/31 WELL TOTAL DEPTH 5350 FEET

OPERATOR: HELMERICH & PAYNE, INC. PRODUCTION CSG: SIZE " FEET

NAME AND 1579 E 21ST SURFACE CASING: SIZE 8 5/8" @ 1903' WITH SX

ADDRESS TULSA, OK 74114

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CHEYENNE DRILLING LICENSE NUMBER 5382

ADDRESS 3728 W JONES AVE, GARDEN CITY, KS 67846

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 31 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM PHIL

(COMPANY NAME) CHEYENNE DRILLING (PHONE) 316-277-2082 RECEIVED STATE CORPORATION COMMISSION

WERE: SEP 08 2000

1ST PLUG AT 3100' WITH 100 SX CEMENT. 2ND PLUG AT 1940' WITH 50 SX CEMENT. 9-8-00

3RD PLUG AT 900' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT. CONSERVATION DIVISION Wichita, Kansas

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH

10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 6:30 PM DAY: 31 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 3100' WITH 100 SX CEMENT. 2ND PLUG AT 1940' WITH 50 SX CEMENT.

3RD PLUG AT 900' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH

10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING

DATE 9/11/00 SIGNED [Signature]

2001060631 (TECHNICIAN) FORM CP-2/3

INVOICED [Signature]

R

[Signature]