

1030337

15-055-10016-0000 7-26-84 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 10-16-59
C SW NE, SEC. 7, T 20²⁶ S, R 20³⁴ W/K

3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Lease Name C.L.Reeve Well # 1

Operator: Champlin Petroleum Company
Name & Address: 6441 N. W. Grand
Oklahoma City, OK 73116

County Finney 168.09

Well Total Depth 5172 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 861

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rosel Perforators License Number _____

Address P. O. Box 1136, Liberal, KS 67901

Company to plug at: Hour: 4:00 pm Day: 9 Month: September Year: 19 82

Plugging proposal received from Bob R Emmert

(company name) Champlin (phone) 316-275-9547

were: 7" set at 5171' Perfs from 4892-5132'

1st plug CIBP set at 4800'

RECEIVED
STATE CORPORATION COMMISSION

2nd plug CIBP set at 1146.

DEC 05 1984 12-5-84

3rd plug pump 25 sx cement in 7"

CONSERVATION DIVISION

4th plug pump 25 sx cement in 7" and 10 3/4" annulus and pressure up

Cut off casing and weld on plate

Plugging Proposal Received by Steve R Emmert (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:30 pm Day: 9 Month: September Year: 19 82

ACTUAL PLUGGING REPORT 7" set at 5171' Perfs from 3892-5132'

1st plug set CIBP at 4800', 2nd plug set CIBP at 1146', 3rd plug pumped 25 sx cement in

7" casing, 4th plug pumped 25 sx cement in 7" and 10 3/4" annulus and pressured up to 700

psi.

Bob Tarbutton observed the plugging

Remarks: No recovery. Used Litewate cement by Halliburton
(If additional description is necessary, use BACK of this form.)

(did not observe this plugging.)

INVOICED

DATE 12-11-84

Signed Steve R Emmert (TECHNICIAN)

INV. NO. 5893