

TECH# 1060108

5-12

API Number 15 -083-20,384 - 0000

State Corporation Commission
Wichita State Office Bldg.
130 S. Market, Room 2078
Wichita, KS 67202

NE NWSE Sec 17 T 24 R 22 W

2310 Feet from S Sect Line
1650 Feet from E Sect Line

OPERATOR

LICENSE# 3871 Lease Name Mellecker Well # 3

Operator: Hugoton Engery County Hodgemen 156.00
Name & Well Total Depth 4800 Feet
Address 1036 E. HYW 40 Production Pipe: Size 5 1/2 Feet 4799
Hays, Ks. 67601 Conductor Pipe: Size Feet
Surface Casing: Size 8 5/8 Feet 696

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereinafter indicated

Plugging Contractor Quality Well Service, Inc. License # 31925

Address 249 Beth Drive Sterling, Ks. 67579-9048

Company to plug at: Hour 12:01pm Day 12 Month 05 Year 98

Plugging Proposal received from: Richard

(company name) Quality Well Service (phone) 785-625-1798

were: Sand bottom off 50' above perforations and 4sxs cement on top of sand. Then cement plug at anhdrite, at permain, bottom surface, then at 40'.

PLUGGING PROPOSAL RECEIVED BY Steve Middleton
(Technician)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour 3:00pm Day 12 Month 05 Year 98

ACTUAL PLUGGING REPORT Sanded bottom to 4391' with 4sxs cement. Then 50sxs cement at 1520'. Then 50sxs at 700'. Then 10sxs at 40'.

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1998 5-19-98

Wichita Kansas

Remarks: Allied Cementing did cement job. Used 60/40 6% gel. Recovered 2630' of pipe.

(DID) / DID NOT) observe this plugging
(circle one)

Signed Michael J. Marie
(Technician) 2/3

INVOICED

DATE 5-21-98
INV. NO. 50593
5-12