

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 15-083-10163-0000

C.S.E. NE 1/4 SEC. 17, T24S, R22W

_____ FEET FROM N/S SECTION LINE

_____ FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5565

LEASE NAME MELLECKER WELL # 1

OPERATOR: NATIONAL COOPERATIVE
NAME & REFINERY ASSOCIATION
ADDRESS Box 6
GREAT BEND, KS 67530

COUNTY HODGEMAN
WELL TOTAL DEPTH 4775' \$ 155.19
FEET

CONDUCTOR PIPE: SIZE _____ FEET

SURFACE CASING: SIZE 8 5/8 FEET 474

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL w/215' of D&A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR KELSO CASING PULLERS LICENSE NUMBER 6050

ADDRESS Box 176, Chase, KS

COMPANY TO PLUG AT: HOUR: 9 AM DAY: 9 MONTH: SEPT YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM NORMAN VOTH

(COMPANY NAME) Kelso (PHONE) _____

WERE: Run 5 1/2" bit @ 4472' w/175' of - PBTD @ 4640 - sand
bottom to 4400 w/5' of cement - (Perfs @ 4453'-61') -
Recovered 1820' - use 60/40 Poz mix w/2% gel &
3% CC and pump 3 sy hulls, 15' of gel, 70' of cement,
10' of gel, 1 sy hulls, release rubber plug and finish
w/150' of cement. PLUGGING PROPOSAL RECEIVED BY R. B. Bartlett
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 10 AM DAY: 9 MONTH: Sept YEAR: 19 83

ACTUAL PLUGGING REPORT Plugged as proposed

Max. pump pressure @ 600#
Shut in pressure @ 200#
Cementing by Sun

REMARKS: Cmt. ticket # 15996

STATE CORPORATION COMMISSION
RECEIVED
SEP 12 1983
CONSERVATION DIVISION
Wichita, Kansas

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

SIGNED R. B. Bartlett ✓
(TECHNICIAN)

INVOICED

DATE 9-28-83

INV. NO. 5565-4

FORM CP-2/3
REV. 6-83