

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Drill completion 9/10/64.

C SW NW, SEC. 16, T 24 S, R 22 W/EX
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5030

Lease Name Schinstock Well # 1

Operator: Vess Oil Corporation
Name & Address: 8100 E. 22nd. N, Bldg. 300
Wichita, KS 67226

County Hodgeman 153.14
Well Total Depth 4712 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address _____

Company to plug at: Hour: 10:30 a.m. Day: 21 Month: 5 Year: 19 97

Plugging proposal received from Bill Horigan

(company name) Vess Oil Corp. (phone) 316-682-1537

Work: 4 1/2" at 4709' w/125 sx cement, Open hole, Pipe parted at 2100-2200'-couldn't get to bottom
Casing squeezed at 2558'

1st plug spot through tubing 30 sx cement on bottom, 5-27-97

2nd plug perforate at 650' and circulate cement to surface,

3rd plug pump 150 sx cement down 8 5/8" X 4 1/2" annulus.

Plugging Proposal Received by Kevin Struber (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 21 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx 60/40 Pozmix 6% gel 3% cc at 2100'. Waited 2 hrs., cement stayed.

2nd plug perforated at 650' and pumped 220 sx cement down casing,

3rd plug pumped 150 sx 60/40 Pozmix 6% gel cement down backside. Had 150# shut in pressure.

Down casing had no pressure-fluid at about 200'.

Remarks: Cemented by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed *Michael J. Moore* (TECHNICIAN)

DATE MAY 29 1997

INV. NO. 48208

5-21 JUL 22 1997

RECEIVED
KANSAS
CORPORATION
MAY 27 4 29