

1 030351

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-083-21,180-0000

C NE SE, SEC. 16, T 24 S, R 22 W EX

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6785

Lease Name Van Nahmen Well # 9-16

Operator: Robert Schulein

County Hodgeman 153.40

Name & Address 1776 Lincoln Street, # 811

Well Total Depth 4720 feet

Denver, CO 80203

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 403

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wildcat Drilling Co. License Number 9180

Address 200 W. Douglas, Suite 250, Wichita, KS 67202

Company to plug at: Hour: 2:00 pm Day: 3 Month: January Year: 19 85

Plugging proposal received from Herb Boxberger

(company name) Wildcat (phone) 316-265-1611

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1440' with 50 sx cement

2nd plug at 840' with 50 sx cement

3rd plug at 420' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:00 pm Day: 3 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1440' with 50 sx cement, 2nd plug at 840' with 50 sx

cement, 3rd plug at 420' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(if additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE 1-22-85

Signed Steve Durrant (TECHNICIAN)

INV. NO. 6627