

1 060059

2-7 083-21,227-0000 158P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-21,227-0000
N/2, SW NE, SEC. 16, T. 24 S, R. 22 W/E

3630 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6785

Lease Name Benish Well # 7-16

Operator: Robert Schulein

County Hodgeman 151.77

Name & Address 1776 Lincoln St., #811

Well Total Depth 4670 feet

Denver, CO 80203

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 413

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Carl W. Durr Consulting License Number

Address RR 1, Box 16A-3, Milton, KS 67106

Company to plug at: Hour 2:50 p.m. Day 7 Month 2 Year 1991

Plugging proposal received from Carl Durr

(company name) Carl W. Durr Consulting (phone) 316-478-2890

were: 5 1/2" at 4660'w/575 sx cement, Open hole at 4660-70', cement circulated to surface

1st plug pump 400 lbs. hulls, 40 sx cement, 20 sx gel, 40 sx cement, gel, and cement.

2nd plug pump annulus if possible.

REC 2-15-91
FEB 15 1991

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour 3:20 p.m. Day 7 Month 2 Year 1991

ACTUAL PLUGGING REPORT 1st plug pumped 400 lbs. hulls, 40 sx cement, 20 sx gel, 40 sx cement.

Annulus pressured up right away.

Maximum pressure 1500 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 2-27-91

Signed (TECHNICIAN)

INV. NO. 30937