

1 070862

10-15

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-20,405-A-0001

SE SW, SEC. 9, T 24 S, R 23 W/EX

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Bill To:
Jim Meyers
Free Point
P.O. Box 271524
OKLA CITY, OK
73137

Lease Name Wade Well # C-1

Operator: Donald C. Slawson Oil Producers

County Hodgeman 156.00

Name & Address 20 N. Broadway, #700

Well Total Depth 4800 feet

Oklahoma City, OK 73102

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 287

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 15 Month: 10 Year: 19 90

Plugging proposal received from Vernon Duntz

(company name) Kelso. Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4799' w/200 sx cement, Perfs at 4711-4711.5'

1st plug sand back to 4660' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 10 sx gel and 50 sx cement at 1470', 3rd plug pump 70 sx cement at 750',

4th plug pump 40 sx cement at 300',

5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 15 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4660' and dumped 4 sx cement on top of sand through bailer,

2nd plug pulled casing to 1400' and spotted 10 sx gel followed with 50 sx cement,

3rd plug pulled to 750' with 70 sx cement,

4th plug pulled to 300' with 40 sx cement,

5th plug topped off with 10 sx cement at 40'

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (check) observe this plugging.

Signed Dan Groder
(TECHNICIAN)

DATE 10-29-90

INV. NO. 29761