

2-24-88

To: 1 061082
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C W/2 NW SE, SEC. 18, T 24 S, R 17 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21,271-0000

1980 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Cross Well # 3-18

Operator: F.G. Holl Company
Name & Address: 6427 East Kellogg
P.O. Box 780167
Wichita, KS 67207

County Edwards 148.1a9

Well Total Depth 4575 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 274

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 24 Month: 3 Year: 1988

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4359' PBSD 4529' Perfs at 4429-35'

1st plug sand back to 4370' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 24 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4370' and dumped 4 sx cement on top of

sand through bailer, 3-28-88

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 130 sx cement.

Maximum pressure 400 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2400' of casing.

(If additional description is necessary, use BACK of this form.)
WICHITA, KANSAS

INVOICED observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 3-29-88

INV. NO. 20238

RECEIVED STATE CORPORATION COMMISSION

MAR 28 1988