

10-3

1 120144

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,388 - 0000
C SE/4, SEC. 18, T 24 S, R 17 W/E

TECHNICIAN'S PLUGGING REPORT

1320 feet from S section line
1320 feet from E section line

Operator License # 5056

Lease Name Cross Well # 1-18

Operator: F.G. Holl

County Edwards 147.55

Name & Address: 6427 East Kellogg
P.O. Box 780167
Wichita, KS 67207

Well Total Depth 4540 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 274

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 3 Month: 10 Year: 1988

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4359' PRTD 4496' Perfs at 4416-20' Elevation 2122' GL

1st plug sand back to 4365' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

10-7-88

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operation attended by Agent?: All Part _____ None _____

Operation started: Hour: 3:30 p.m. Day: 3 Month: 10 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4365' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2428' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(If desired, observe this plugging.)

INVOICED

DATE 10-10-88

Signed [Signature]
(TECHNICIAN)

INV. NO. 22559