

To: 1 090746  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

10-24

API NUMBER 15-047-21,382-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

SW SW NW, SEC. 18, T 24 S, R 17 W/E  
2970 feet from S section line  
4950 feet from E section line

Operator: F.G. Holl Company LLC  
Name:  
Address P.O. Box 780167  
Wichita, KS 67278-0167

Lease Name Cross A Well # 2-18  
County Edwards 144.30  
Well Total Depth 4440 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12:30 p.m. Day: 24 Month: 10 Year: 19 96

Plugging proposal received from Thom Pool

(company name) F.G. Holl Co. (phone) 316-793-0289

Work: 5 1/2" at 4422' w/225 sx cement, Open hole 4422-4440'  
1st plug sand back to 4370' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:15 p.m. Day: 24 Month: 10 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4370' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2550' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

I (did / ~~XXXXXX~~) observe this plugging.

DATE 10-24-96

INV. NO. 46848

Signed [Signature]  
(TECHNICIAN)

REC'D  
OCT 28 1996  
D. E. H. H.