

To: **1 051847** **10-7**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200, COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,304-0000  
C NE NE, SEC. 24, T. 24 S, R 17 WXX  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5420  
Operator: White & Ellis Drilling, Inc.  
Name & Address: P.O. Box 48848  
Wichita, KS 67201-8848

Lease Name Mc Intyre Well # 1  
County Edwards  
Well Total Depth 4400 143.00 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service, Inc. License Number 5893  
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11 a.m. Day: 7 Month: 10 Year: 19 94  
Plugging proposal received from Fred Mease  
(company name) Pratt Well Service, Inc. (phone) 316-672-2531

vers: 4 1/2" at 4390' w/125 sx cement, PBD 4353', Perfs at 4312-22'  
1st plug sand back to 4260' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 500 lbs. hulls, 20 sx gel and 200 sx cement down 4 1/2" casing.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3:30 p.m. Day: 7 Month: 10 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4260' and dumped 4 sx cement on top of sand through bailer,  
Pumped a hole in the 8 5/8" **10-12-94**

2nd plug ran tubing to 1030' and circulated cement to surface with 200 sx cement  
RECEIVED STATE CORPORATION COMMISSION  
OCT 12 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2271' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)  
Observe this plugging.

INVOICED  
DATE 11-3-94 Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 41580  
FORM CP Rev. 1