

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21, 146-0000

NW/4 Sec. 24, T24 S, R17 WX

660 feet from NX section line

3300 feet from X/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name KELLER G Well # 1

Operator: VAC PETROLEUM
Name & Address 6225 E. KELLOGG
WICHITA, KS 67218

County EDWARDS

Well Total Depth 4450 feet 144.62

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 458

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor COUGAR DRILLING CO. License Number 5138

Address 555 N. WOODLAWN #14, WICHITA, KS 67208

Company to plug at: Hour: 2 AM Day: 15 Month: JAN Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO GARY BAGBY

(company name) COUGAR (phone)

were: TO USE 60/40 Pozmix, w/ 2% gel - 3% CC AND SPOT THE
1ST plug @ 1110' w/ 50 syx - 2ND plug @ 570 w/ 40 syx
3RD plug @ 40' w/ solid bridge of mulls, wiper
plug and 10 syx to the surface. Circulate 15 syx
in the rat hole, 10 syx in the mouse hole. Plug water
well w/ 5 syx.

Signed R. Bartlett
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:30 AM Day: 15 Month: JAN Year: 1984

ACTUAL PLUGGING REPORT Plugged as ordered. Cement plugs
spotted through drill pipe in heavy mud.
Cementing by Halliburton, Ticket # 705859.

Remarks:

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~ did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1984
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 1-20-84
INV. NO. 9220 W

Signed R. Bartlett
(TECHNICIAN)