

1030561

API NUMBER 15- 047-20,871 - 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SW , SEC. 35 , T 24 S, R 17 W/EX
4840 feet from S section line
440 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Hawley "C" Well # 2-35

Operator: F. G. Holl
Name & Address: 6427 East Kellogg
Wichita, KS 67207

County Edwards
Well Total Depth 4555 148.04 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 287

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 28 Month: October Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4550' Perfs at 4409-13' PBTD 4553

1st plug sand back to 4350' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00 pm Day: 28 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 300 psi and shut in 50 psi.

Remarks: Recovered 2300' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 11-1-85
INV. NO. 10863

RECEIVED 11-1-85
STATE CORPORATION COMMISSION
Signed Steve Drennon (TECHNICIAN)

NOV 1 1985
CONSERVATION DIVISION