

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- -

~~NW 1/4~~ SEC. L, T. 24S, R. 18W

440 FEET FROM ~~N~~ SECTION LINE

440 FEET FROM ~~W~~ SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5056

LEASE NAME WHITE WELL # 1-1

OPERATOR: F.G. Holl
NAME & ADDRESS 6427 E. Kellogg
WICHITA, KS 67207

COUNTY EDWARDS

WELL TOTAL DEPTH 4600 \$149.50 FEET

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 5/8 FEET 281

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Kelso Casings Pulling LICENSE NUMBER 6050

ADDRESS Box 347, Chase, KS 67524

COMPANY TO PLUG AT: HOUR 11:45pm DAY: 19 MONTH: AUG YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM Bob Branneman

(COMPANY NAME) Kelso (PHONE) _____

WERE: 4 1/2" @ 4599' w/ 2300' recovered - Perfs. @ 4383' to 4387'
bottom sandbed to 4320' plug & set cmt - hole plugged
by pumping 2 sy hulls, 15 sy gel, 70 sy cmt, 15 sy gel
1 sy hulls, 4 1/2 rubber plug & 80 sy. cement using
60/40 poz mix, 2% gel - 3% CC.

PLUGGING PROPOSAL RECEIVED BY R. Barlittan
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR 2:45pm DAY: 19 MONTH: AUG YEAR: 19 83

ACTUAL PLUGGING REPORT plugged as proposed.

Max. pump pressure 500#
Shut in - 0# w/ no vacuum
Cementing by Allied.

8-26-83

REMARKS: Cementer to call in plug top

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1983
Wichita, Kansas

I Did (~~did not~~) OBSERVE THIS PLUGGING.

SIGNED R. Barlittan
(TECHNICIAN)

INVOICED

DATE 8-26-83

INV. NO. 5355-W