


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Hodgeman County. Sec. 4 Twp. 24S Rge. 21 (E) (W) X  
Location as "NE/CNW/SW" or footage from lines C SE SW  
Lease Owner Colorado Oil & Gas Company  
Lease Name Burke Well No. A-1  
Office Address 1020 Hoover Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 4-1-66 19\_\_\_\_  
Plugging completed 6-30-66 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well PB 4753 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	251	None
				5 1/2	None	2631

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in. Cleaned out cellar. Measured TD. Pumped in 20 sacks of cement to 4100'. Working pipe. Shot pipe at 4100' and 4030'. Pumping mud and cement. Circulating. Spotted 100 bbl. of oil. Working pipe. Shot pipe at 3804' - 3619' - 3403' - 3211' - 3007' - 2812 - 2608'. Pulling pipe. Moved in wire line rig. Rigging up. Set in jacks and spider. Worked pipe loose. Pulling pipe. Working pipe. Pulling pipe. Squeezed well with 30 sacks of cement at 700' to 600'. Dumped 35 sacks of cement and 20 bbl of mud. Dumped 7 bbl of mud and 10 sacks of cement. Well completed.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 11 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of July, 19 66

My commission expires May 27, 1969

Notary Public.

COLORADO OIL & GAS CORP. - Operator

SIERRA PETROLEUM CO., INC. - Contractor

DURKE A#1  
 C SE SW  
 Sec. 4-21S-21W  
 Hodgeman County, Kansas

T. D.: 4753'  
 Elev.: 2365' K.R.

Commenced: 10-23-63  
 Completed: 11-10-63

Casing:

8-5/8" Set at 250'  
 5-1/2" Set at 4752'

Cement:

with 200 ex. Common  
 with 125 ex. Pozmix

FORMATION

DEPTH

Surface Clay  
 Sand Rock & Sand  
 Shale & Shells  
 Shale  
 Red Bed & Shale  
 Anhydrite  
 Shale  
 Sand  
 Shale & Red Bed  
 Anhydrite  
 Shale, Shells & Red Bed  
 Shale & Lime  
 Lime  
 Lime & Shale  
 Lime  
 Mississippi  
 Lime & Chert

30  
 90  
 250  
 675  
 821  
 835  
 915  
 1035  
 1445  
 1461  
 1650  
 2620  
 2950  
 3910  
 4682  
 4745  
 4753

STATE OF KANSAS )  
 ) ss:  
 COUNTY OF RUSSELL )


I hereby certify that the above information is true and correct to the best of my knowledge.

C. T. Honaker  
 Drilling Superintendent

Subscribed and sworn to before me this 12th day of November, 1963.

Leroy Dietz  
 Notary Public

My commission expires: 10-17-67



**RECEIVED**  
 STATE CORPORATION COMMISSION

FEB 17 1966