


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Reno County, Sec. 7 Twp. 22S Rge. 4 E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
NW SW SW

Lease Owner A. Scott Hitchie  
Lease Name Janzen Well No. 1  
Office Address 412 Union Center, Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed Aug. 30 1976  
Application for plugging filed Aug 30 1976  
Application for plugging approved Aug 30 1976  
Plugging commenced Aug 30 1976  
Plugging completed Aug 30 1976  
Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3870  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Bottom plug at 500' w/40 sacks 50/50 Pozmix, 2% Gel.

Middle plug @ 250' w/25 sacks 50/50 Pozmix, 2% Gel.

Top plug @ 40' w/1/2 sack hulls and 10 sacks 50/50 Pozmix, 2% Gel.

RECEIVED  
CORPORATION COMMISSION

SEP 02 1976

9-2-76  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.  
Wayne Dobbs (employee of owner) or (OWNER)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature)

Wayne Dobbs

Box 823, Great Bend, Ks. 67530

(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1976

Deborah M. Nague  
Notary Public.

My commission expires April 11, 1978

DRILLERS' WELL LOG

DATE COMMENCED: August 21, 1976  
 DATE COMPLETED: August 30, 1976

A. Scott Ritchie  
 JANZEN # 1  
 NW SW SW  
 Sec 7-T22-R4  
 Reno County, Kansas

ELEVATION: 1483 K.B.

0 - 40'	Clay
40 - 263'	Shale, Shells, Sand Streaks
263 - 1415'	Shale
1415 - 2432'	Shale and Lime
2432 - 2436'	Shale
2436 - 2463'	Lime and Shale
2463 - 2656'	Shale
2656 - 3088'	Lime
3088 - 3346'	Lime and Shale
3346 - 3583'	Chert and Lime
3583 - 3711'	Shale
3711 - 3842'	Sand
3842 - 3859'	Chert
3859 - 3863'	Shale
3863 - 3870'	Sand
3870'	RTD

FORMATION TOPS

Heebner	2432
Douglas	2463
Lansing	2656
Base K.C.	3088
Mississippi	3346
Kinderhook	3583
Hunton	3711
Viola	3842
Simpson Shale	3859
Simpson Sand	3863
RTD	3870

SURFACE PIPE:  
 Set used 8 5/8", 23# pipe @ 263'  
 w/185 sacks Common, 2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS }  
 COUNTY OF BARTON } ss.

Wayne Dobbs, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Wayne Dobbs

Subscribed and sworn to before me this 31st day of August, 1976.

Deborah M. Hague  
 Notary Public

My Commission Expires: April 11, 1978

STATE OF KANSAS  
 CONSERVATION DIVISION

SEP 02 1976

Wichita, Kansas

9-2-76