


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-155-00241-0000
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
808 Bitting Building
Wichita, Kansas

Reno County. Sec. 18 Twp. 22 Rge. (E) 4 (W)
Location as "NE/CNW%SW%" or footage from lines SW SW SE
Lease Owner Musgrove Petroleum Corporation
Lease Name ADRIAN Well No. 1
Office Address 518 Petroleum Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed November 12 1955
Application for plugging filed verbally - November 11 1955
Application for plugging approved verbally - November 11 1955
Plugging commenced November 12 1955
Plugging completed November 12 1955
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, Box 597, McPherson, Ks.
Producing formation Depth to top Bottom Total Depth of Well 3874 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	296'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 270'
Set 1st plug at 270' w/ 1/2 sk hulls & 15 sx cement
Filled hole with heavy mud to 5' from bottom of cellar
Set 2nd plug at 12' w/ 1/2 sk hulls & 5 sx cement

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Musgrove Petroleum Corporation
Address 518 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick ss.
I, Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of November, 19 55

Alma E. Lane
Notary Public.

My commission expires July 16, 1959

24-7966-5 3-53-20M

PLUGGING
FILE SEC 18 T. 22 R. 4W
BOOK PAGE 66 LINE 6

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1955 11-18-55
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

15-155-00241-0000

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: ADRIAN #1
 LOCATION: SW SW SE, Sec. 18-22-4
 Reno County, Kansas
 COMMENCED: October 27, 1955
 COMPLETED: November 12, 1955

0	40	Surface soil & sand
40	110	Sand & Sandy clay
110	260	Sand, shale & shells
260	298	Blue shale & lime
298	450	Shale & lime
450	620	Shaled lime streaks
620	735	Anhydrite & shale
735	810	Anhydrite
810	940	Anhydrite, lime & shale
940	1310	Lime & shale
1310	1982	Shale & lime streaks
1982	2145	Shale & lime
2145	2210	Shale & lime streaks
2210	2275	Lime & shale
2275	2325	Lime
2325	2560	Lime & shale
2560	2630	Shale w/lime streaks
2630	2744	Lime & shale
2744	3175	Lime
3175	3330	Lime & shale
3330	3355	Cherty lime & shale
3355	3380	Lime, shale & chert
3380	3465	Cherty lime & shale
3465	3615	Cherty lime
3615	3685	Lime & shale
3685	3720	Shale, sand & lime
3720	3834	Lime & shale
3834	3848	Lime, shale & sand
3848	3858	Sand
3858	3874	Lime & shale
	3874	Rotary Total Depth

Set 8-5/8" surface casing at 296' w/200 sx Posmix & 100 sx cement.

Dry and Abandoned

ELEVATION:	1464' K. B.	Kinderhook:	3576'	3580'
TOPS:	Sample Schlumbr	Hunton:	3712'	3718'
Lansing	2633'	Viola:	3827'	3832'
Cherty Cong.	3329'	Simpson Sd.	3844'	3850'
Miss. Lime	3349'			

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Gordon L. Koelling, do hereby certify that the above and foregoing is a true and correct copy of the log of the ADRIAN #1, SW SW SE, Section 18-22-4, Reno County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY *Gordon L. Koelling*
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 16th day of November, 1955.

PL
 FILE SEC. 18-22-R-4W
 BOOK PAGE 16 LINE 6

Gordon L. Koelling
 Notary Public

My commission expires July 16, 1959

RECEIVED
 Notary Public

NOV 18 11-18-55
 CONSERVATION DIVISION