

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail, or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-155-00309-0000
WELL PLUGGING RECORD

Reno County, Sec. 18 Twp. 22 Rge. 4 #E (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NW

Lease Owner Glickman Oil Company

Lease Name Edigar Well No. 1

Office Address 439 S. St. Francis

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed April 4 19 52

Application for plugging filed " 19 "

Application for plugging approved " 19 "


Plugging commenced " 19 "

Plugging completed " 19 "

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3963 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4"	180'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole full heavy mud to 180' of top, drove wooden plug to 180' and dumped in ²⁰/₅ sacks cement. Finished filling hole with heavy mud to within 35' of cellar, and dumped in 5 sacks cement.

4-15-52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mallard Drilling Company

Address 1016 Union National Bank Bldg.

STATE OF Kansas, COUNTY OF Sedgwick

A. H. Perks, partner (employee of owner) or (owner or operator) of the above-described well,


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. H. Perks

(Address)

SUBSCRIBED AND SWORN to before me this 9th day of April, 1952

My commission expires 12/4/52 Notary Public.



COMPANY: GLICKMAN OIL COMPANY
 CONTRACTOR: MALLARD DRILLING COMPANY
 FARM: EDIGAR #1
 LOCATION: SW SW NW, Sec. 18-22-4W
 Reno County, Kansas
 COMMENCED: March 21, 1952
 COMPLETED: April 4, 1952

0	to	70	Surface sand
70	to	180	Lime and shale
180	to	524	Shale and shells
524	to	900	Lime
900	to	1100	Shale and lime
1100	to	1210	Lime
1210	to	1515	Shale and shells
1515	to	2220	Shale and lime
2220	to	2360	Lime
2360	to	2560	Lime and sand
2560	to	3023	Lime
3023	to	3340	Lime and shale
3340	to	3462	Lime and chert
3462	to	3493	Lime
3493	to	3581	Lime and chert
3581	to	3670	Shale
3670	to	3830	Lime and shale
3830	to	3841	Shale
3841	to	3853	Viola Lime
3853	to	3864	Lime and sand
3864	to	3898	Sand
3898	to	3943	Sand and shale
3943	to	3963	Arbuckle
		3963	T.D.

Set 180 feet of 10 3/4" surface pipe. Cemented with 165 sacks cement.

TOPS: Simpson -- 3658 Viola -- 3843 ³⁶⁷⁰

Measurements taken from derrick floor

DRY, ABANDONED AND PLUGGED

C E R T I F I C A T E

I, A. H. Parks, do hereby certify that the above and foregoing is a true and correct copy of log of the Edigar #1, SW SW NW, Sec. 18-22-4W, Reno County, Kansas.

A. H. Parks

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 9th day of April 1952.

Spencer Wright

My commission expires 12/4/52

4-16-52

PLUGGING
 FILE SEC. 18-22-4W
 BOOK PAGE 6 UNIT 34