


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno County, Sec. 22 Twp. 22S Rge. (E) 4 (W)
Location as "NE/CNW&SW" or footage from lines. SW NW
Lease Owner Natural Gas and Oil Company
Lease Name Becker Well No. 1
Office Address P. O. Box 105, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-3 19 59
Application for plugging filed 5-4 19 59
Application for plugging approved 5-4 19 59
Plugging commenced 5-4 19 59
Plugging completed 5-4 19 59
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gene Graham, Winfield, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3983 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	260	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240 feet
Plug, 1/4 sack hulls, 15 sacks cement at 240 feet.
Heavy mud to 25 feet
Plug, 1/4 sack hulls, 8 sacks cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1959
CONSERVATION DIVISION
WICHITA, KANSAS
5-5-59

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Greenland Drilling Company
Address P. O. Box 518 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
J. B. Steele, Jr. (employee of owner) ~~W. B. Steele, Jr.~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Steele, Jr.
P. O. Box 105 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of May, 19 59

Richard R. Brack
Notary Public.

My commission expires July 27, 1959

PLUGGING
FILE SEC 22 22 R 40
BOOK PAGE 35 LINE 35

WELL LOG

15-155-00349-0000

Company: NATURAL GAS & OIL COMPANY

Sec. 22 Twp. 22s Rge. 4w

Farm: BECKER No. 1

Location: C SW NW

Reno County, Kansas

Commenced: 4-16-59

Completed: 5-4-59

Total Depth: 3983

Contractor: GREENLAND DRILLING COMPANY

Casing: 8-5/8" 260'
5-1/2" ----

Elevation: 1461 R.B.

Production: D & A

Figures Indicate Bottom of Formations

125	Shale w/streaks sand	TOPS: Heebner	2380
260	Shale & shells	Brown Lime	2580
580	Shale & shells	Lans.-Kans. City	2610
985	Lime	Base K.C.	3050
1165	Sandy lime & shale	Mississippi	3326
1210	Lime	Kinderhook	3592
2095	Shale & lime	Hunton	3734
2335	Lime	Viola	3859
2410	Lime w/shale breaks	Simpson	3875
2551	Shale	Arbuckle	3962
2594	Lime	RTD	3983
2610	Lime & shale		
3050	Lime		
3169	Lime & shale		
3326	Shale & lime		
3591	Lime		
3610	Lime & chert		
3623	Shale & lime		
3719	Shale		
3745	Hunton		
3792	Shale & sand		
3809	Shale & lime		
3859	Shale		
3875	Viola		
3890	Simpson sand		
3930	Shale & lime		
3962	Sand & shale		
3983	Lime		
3983	RTD		

STATE OF KANSAS
STATE BOARD OF GEOLOGICAL SURVEY

MAY 7 1959

CONSERVATION DIVISION
Wichita, Kansas

5-7-59

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Oscar Bridge, of the Greenland Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Becker well.

Oscar Bridge
Oscar Bridge, Vice-President

Subscribed and sworn to before me this 5th day of May, 1959.

Verdina B. Rutledge
Verdina B. Rutledge, Notary Public

My commission expires March 15, 1960.

PLUGGING

FILE SEC 22 T. 22 R. 4W
BOOK PAGE 35 LINE 35

MAY - 6 1959