


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-155-00026-0000

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Reno County. Sec. 5 Twp 22S Rge 5 (E) W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SE
Lease Owner Beardmore Drilling Company
Lease Name Rice Well No. 1
Office Address 827 Beacon Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-14 19 56
Application for plugging filed 3-13 19 56
Application for plugging approved 3-13 19 56
Plugging commenced 3-14 19 56
Plugging completed 3-14 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well 4061 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand		0	60			
Shale and Shells		60	186	8 5/8"	186	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

0 - 35' - 5 sacks cement
35' - Wood Plug
35 - 135' - Heavy Mud
135 - 180' - 15 sacks cement
180' - Wood Plug
180 - 4061' - Heavy Mud

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to
Name of Plugging Contractor - Beardmore Drilling Company
Address - 827 Beacon Building - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Heber Beardmore (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *Heber Beardmore*

827 Beacon Building
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of March, 19 56

Leonard P. Tolle
Leonard P. Tolle Notary Public.

My commission expires January 28, 1960



3-21-56

15-155-00026-0000

BEARDMORE-SUTTON

#1 Rice
NE NE SE Section 5-22S-5W
Reno County, Kansas

Drilled By: Beardmore Drilling Company
Drilling Commenced: 3-3-56
Drilling Completed: 3-14-56

Casing Record:

Ran 188' of 8 5/8" set at 186' with 125 sacks cement.
Cement circulated. 3-3-56.

Elevations: KB 1534
DF 1531
Gr 1528

<u>FORMATIONS</u>	<u>DEPTH</u>
Cellar	5
Sand and Shale	60
Shale and Shells	186
Shale and Shells	640
Shale and Lime	1030
Lime	1475
Shale	1890
Shale and Lime	2350
Sand	2720
Shale and Lime	2850
Lime	2932
Shale and Lime	3040
Lime	3215
Shale and Lime	3330
Shale	3480
Lime	3505
Lime and Chert	3540
Lime	3643
Lime and Shale	3710
Shale	3780
Shale and Lime	3830
Sand	3990
Shale	4000
Shale and Lime	4035
Rotary Total Depth	4061

TOPS

Lansing	2799
Warsaw Limestone	3436
Osage Chert	3486
Kinderhook Shale	3667
Viola	3926
Simpson Shale	3948
Simpson Sand	3951
Arbuckle	4030

DST #1 - 3473-3540 - Shut in 15 min. - good blow for one hour - shut in 15 min. Recovered 1980' salt water. IBHP 1065 - FBHP 1020 - IF 140 - FF 980.

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above-described, to the best of my knowledge and belief.

3-21-56 Robert J. Gutru
Robert J. Gutru

Subscribed and sworn to before me this 19th day of March, 1956.

Leonard P. Tolle
Leonard P. Tolle - Notary Public

My Commission Expires:
January 28, 1960

PLUGGING			
FILE	SEC	T	R
	5	22	5W
BOOK	PAGE	LINE	
	45	44	