

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-155-03113-0000
API NUMBER 6-27-36

LEASE NAME Bartel

WELL NUMBER 2

660 Ft. from (S) Section Line

1650 Ft. from (E) Section Line

SEC. 36 TWP. 22 RGE. 4 (E) or (W)

COUNTY Reno

Date Well Completed 6-27-36

Plugging Commenced 2-7-95

Plugging Completed 2-8-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Bear Petroleum, Inc.

ADDRESS Box 438 Haysville, KS 67060

PHONE# (316) 524-1225 OPERATORS LICENSE NO. 4419

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-7-95 (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Miss Depth to Top 3271 Bottom 3447 T.D. 3447

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content Surface	From Surface	To 297	Size 12 1/2"	Put in 297	Pulled out 0
	Production	Surface	3271	7"	3347	600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Dumped sand from 3347' to 3221' dump bailed 10 sax cement on sand, recoverable casing ran in hole 600' 2" tubing spotted 35 sax at 600' pulled tubing to 350' circulated cement to surface, pulled tubing, filled hole with cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Oil Field Service, Inc. License No. 3004 STATE COMMISSION

Address Box 607 Burrton, KS 67020

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bear Petroleum, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

FEB 28 1995
2-28-95
CONSERVATION DIVISION
WICHITA, KANSAS

R.A. Schremmer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R.A. Schremmer

(Address) Box 438 Haysville, KS 67060

SUBSCRIBED AND SWORN TO before me this 7th day of February, 19 95

DEBRA K. HILL-JOHNSON
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. Apr. 15, 1995

Debra K. Hill-Johnson
Notary Public
Debra K. Hill-Johnson

My Commission Expires: April 15, 1995

15-155-6313-0000

OPERATOR: F. H. Hollow et al Inman, Ks.
RECORD OF WELL NO. 2: D. B. Bartel Farm.
LOCATION: SE corner W/2 SW/4 Section 36-22s-4w Reno County, Kansas.
CONTRACTOR: The McPherson Drilling Company.
Commenced Drilling: June 27, 1936.
Completed Drilling: August 15, 1936.
Casing record: 12 1/2" 50# 297' Cemented with 225 Sax Cement.
7" O.D. 24# 3271' Cemented with 100 Sax Cement.

LOG:

Sand & Clay	230	Lime	2783
Broken Lime	297	Shale	2808
Broken Lime	1036	Lime	2882
Broken Lime	1070	Porous Lime	2890
Lime	1085	Lime	2969
Shale & Red Rock	1118	Shale	2973
Shale	1200	Lime	3009
Shale	1270	Shale	3164
Broken Lime	1292	Shale, Vari Colored	3180
Shale & Shells	1350	Lime, broken	3188
Broken Lime	1736	Shale	3254
Shale	1814	Chatt	3280
Broken Lime	1925	Chat, soft	3288
Shale	1958	Chat, hard	3295
Lime	1964	Chat, hard	3325
Broken Lime	2041	Chat, soft	3345
Shale	2130	Oil at 3335	
Broken Lime	2146	Show of gas at 3295	
Lime	2207	Drove 2 1/2" lead wool.	
Broken Lime	2380	Total depth after driving wool	
Sandy Lime	2408	plug, 3342 1/2'	
Shale	2535		
Broken Lime	2540	Drilled out lead wool--new total	
Shale	2570	depth 3347.	
Lime	2650		
Sandy Lime	2690		
Porous Lime	2717		

*Initial Potential 8/7 131 bbls AT. 8/3-2000 gal
8/18 217 bbls - 1/18 3000 gal.*

STATE CORPORATION COMMISSION

FEB 28 1935

2-28-95

CONSERVATION DIVISION
WICHITA, KANSAS