

WELL-PLUGGING-RECORD

Dta  
initials

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division,  
State Corporation Commission,  
800 Bittling Building,  
Wichita, Kansas.

RECEIVED

SEP 20 1935

9-20-35

BY NORTH 22S

Reno

County. Sec. 36 Twp. 22S Rge. (E) 4 (W)

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging-off formations.

SE	SW	SW
		36.
		No. 1.

Locate well correctly on above 640 A. Plat

Lease Name. Abraham Dick WELL NO. 1.  
 Lease Owner. W. C. McBride, Inc.,  
 Office Address. 1226 Olive Street, St. Louis, Missouri.  
 Character of Well (Oil, Gas or Dry) Dry Total Depth of Well 3397 Feet  
 Date, well, completed September 7, 1935.  
 Application for plugging and log of well filed September 8, 1935.  
 Application for plugging approved September 8, 1935.  
 Plugging Commenced September 10, 1935.  
 Plugging Completed September 15, 1935.

Reason for abandonment of well or producing formation Dry.

If a producing well is abandoned, date of last production -- 193--

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Officer who supervised plugging of this well Alexander

Producing formation..... Depth to top..... Bottom.....

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Chat	Very S.S. Oil	3295	3300	15 1/2"	278	None
	S.O. & Gas	3310	3314	13-3/8"	602	459'
	1/2 bailer Oil			8-5/8"	3273	2742'
	in 3 hrs.	3322				
	3 bailers water	3344	3350			
	600' Oil & water in hole	T.D.	3397			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3397 feet to surface feet for each plug set.

Three hundred (300) feet heavy mud dumped with bailer. After 8-5/8" casing started, hole filled to surface with mud, placed with steam jet. After 13-3/8" pipe pulled - hole was filled to surface, then cement plug placed in 15 1/2" surface casing.

PLUGGING  
FILE SEC 36 T 22 R 4 W  
BOOK PAGE 17 LINE 30

(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations? Yes.

Was exception made?..... If so describe.....

Correspondence regarding this well should be addressed to W. C. McBride, Inc.,

Address Grand Building, McPherson, Kansas.

STATE OF Kansas. COUNTY OF McPherson, ss.

Frank Zimmerman (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Zimmerman

(Address)

SUBSCRIBED AND SWORN to before me this 19th day of September, 1935.

David Paoli

My commission expires July 15, 1939.

Notary Public.







3107

3132  
3255  
3262  
3278  
3322  
3370  
3377  
3388  
3397

Shale & Lime Shells  
Shale  
Shale & Lime  
Chat  
Lime  
Chat  
Sand (Hard & White)  
Sandy Lime  
Lime

PLUGGING	
FILE SEC	26T-22R4W
BOOK PAGE	17 NE 30