

15-155-19149-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno

County. Sec. 36 Twp. 22S Rge. 4W (E) (W)

T 22S NORTH R 4W

Location as "NE/CNW&SW" or footage from lines CS/2 NE SE

Lease Owner Frank J. Black

Lease Name Peters Well No. 1

Office Address 600 W. Washington - McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed April 24 19 55

Application for plugging filed June 14 19 56

Application for plugging approved June 15 19 56

Plugging commenced June 27 19 56

Plugging completed June 29 19 56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production May 19 56

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Ruel Durkee

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3330 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	300'	None
				5-1/2"	3330'	2993'
				Pipe perforated from 3302' to 3309'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled the hole with sand from 3330' to 3290' and ran 6 sacks of cement. Mudded the hole to 300', set a 10' rock bridge and ran 15 sacks of cement. Mudded the hole to 25', set a rock bridge and ran 5 sacks of cement to fill to base of cellar. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

(Address)

SUBSCRIBED AND SWORN to before me this 7 day of July 1956

My commission expires 2-15-58

[Handwritten Signature] Notary Public.

PLUGGING
FILE SEC 36 T 22 R 4W
BOOK PAGE 71 LINE 22

79-56

15-155-19149-0000


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- RAYMOND GEAR & FRED RUST
Farm- Peters No. 1

SEC. 36 T. 22 R. 4W
CS/2 NE SE

Total Depth. 3330
Comm. 4-12-55 Comp. 4-24-55
Shot or Treated.
Contractor. Lewis Drilling Co.
Issued. 6-4-55

County Reno KANSAS



CASINGS:
8 5/8" 300'
5 1/2" 3330'

Elevation. 1116 ft. B.

Production. Swab 26 BOPD @ 24 ft.
30 BW

Figures indicate Bottom of Formations

sand 200
shale blue 475
anhydrite 520
shale, lime. 2925
lime 2970
lime, shale 3085
lime 3330 RTD
Cable Tools
lime 3344
Total Depth

Tops:
Mississippi lime 3245

Acidized w/1000 gal. 3320-3344

Perforated 21 shots 3302-3309

PLUGGING
FILE SEC. 36 T. 22 R. 4W
BOOK PAGE 71 LINE 22

STATE RECORDS
JUN 9 1955
CONSERVATION DIVISION

7-9-56