

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S.-Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-055-21690-0000

LEASE NAME Mary Jones

WELL NUMBER 3

650 Ft. from S Section Line

1140 Ft. from E Section Line

SEC. 34 TWP. 26S RGE. 34 (E) or (W)

COUNTY Finney

Date Well Completed 8-31-00

Plugging Commenced 9-1-00

Plugging Completed 9-1-00

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS 1579 E. 21st Tulsa, OK 74114

PHONE (918) 742-5531 OPERATORS LICENSE NO. 5293

Character of Well D&A

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 8-23-00 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation NA Depth to Top NA Bottom NA T.D. 5350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 10-25-00

Formation	Content	From	To	Size	Put In	Pulled out
Dry Hole		0	1903	8 5/8	1903	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:

From 5350' to 3100' - Mud From 1850' to 900' - Mud
 3100' to 2900' - 100 sx cement 900' to 750' - 40 sx cement
 2900' to 1940' - Mud 750' to 40' - Mud
 1940' to 1850' - 50 sx cement 40' to 3' - 10 sx cement

Rathole 15 sx cement, Mousehole 10 sx cement.

Name of Plugging Contractor Cheyenne Drilling License No. 5382

Address 3728 W. Jones Ave, Garden City, KS 67846

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Sharon LaValley, Engineer Tech (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Sharon LaValley

(Address) 1579 E. 21st, Tulsa, OK 74114

SUBSCRIBED AND SWORN TO before me this 23rd day of October 2000

Teresa Marie Handberg
 Notary Public
 My Commission Expires: August 17, 2002