



Locate well correctly on above Section Plat

Edwards County, Sec. 32 Twp. 24S Rge. 19 (E) W (W)  
 Location as "NE/CNW&SW" or footage from lines C SW SW  
 Lease Owner Homer E. Ogden or Emil E. Ogden et al  
 Lease Name Herrmann Well No. 1  
 Office Address Kinsley, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed August 26, 19 57  
 Application for plugging filed August 26, 19 57  
 Application for plugging approved August 26, 19 57  
 Plugging commenced August 26, 19 57  
 Plugging completed August 27, 19 57  
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4820 Feet  
 Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	278'	8 5/8"	278'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

From 4820' to 275' - heavy rotary mud  
275' to 213' - plug and 20 sacks cement  
213' to 35' - heavy rotary mud  
35' to 6' - plug, 1/2 sacks hulls, 10 sacks cement  
6' to surface - cellar

9-7-57  
 STATE CORPORATION COMMISSION  
 SEP 7 1957  
 DIVISION

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Glenn W. Peel  
 Address P.O. Box 359, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Glenn W. Peel (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. GLENN W. PEEL

By: Jack Mattuck  
 (Signature) P.O. Box 359, Hoisington, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August, 19 57

Ruth Brant  
 Notary Public.

My commission expires April 27, 1960

**PLUGGING**  
 FILE SEC. 32 T. 24 R. 19 W  
 BOOK PAGE 41 LINE 7

DRILLERS' LOG

Company: Homer E. Ogden or Emil E. Ogden, et al

C SW SW

Farm Name: Herrmann Well No. 1

Sec. 32, Twp. 24S, Rge. 19W,

Total Depth: 4820'

County: Edwards, Kansas

Commenced: 8/9/57 Completed: 8/27/57

Elevation:

Contractor: Glenn W. Peel

Production: Dry

Casing: 8 5/8" @ 278' cem.

Figures below indicate bottoms of formations:

Sand and clay	0	80
Sand		100
Sand, white shale, blue shale		278
Blue shale		510
Red bed		1050
Shale and shells		1195
Red bed		1321
Anhydrite		1335
Shale		1790
Shale and shells		1990
Lime		2005
Shale		2150
Sand lime		2200
Lime		2690
Lime and shale		2811
Lime		2955
Lime and shale streaks		3040
Lime and shale		3135
Lime		3235
Shale and lime		3355
Lime		3410
Lime and shale streaks		3550
Lime		3960
Shale		4020
Brown lime		4030
Lime		4488
Lime and shale streaks		4550
Lime		4570
Core		4602
Lime		4603
Core		4612
Chert		4620
Chat		4655
Chert and lime		4685
Lime and cherty streaks		4730
Lime		4755
Sand and chert		4790
Lime and chert		4820
Total Depth		4820

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEEL

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 27th day of August, 1957

My commission expires: April 27, 1960

Ruth Brank  
Notary Public

RECEIVED  
STATE COMMISSION

12-27-57

DEC 27 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
SEC. 32 T. 24 R. 19 W.  
BOOK PAGE 41 LINE 4