

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-047-20394-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County, Sec. 32 Twp. 24-S Rge. 19W R/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
W/2 SW SW

Lease Owner ZENITH DRILLING CORP., INC.
Lease Name Herrmann #1 Well No. 1
Office Address Suite 600, 200 W. Douglas, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed June 19, 1978 19
Application for plugging filed June 18, 1978 19
Application for plugging approved June 18, 1978 19
Plugging commenced 2:00 A.M. June 19, 1978 19
Plugging completed 3:00 A.M. June 19, 1978 19
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3481'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	295'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud pumped thru open ended drill pipe;
40 sacks at 600' and 40 sacks at 300';
solid bridge at 40' with plug and 1/2 sack
hulls and 12 sacks to surface; 3 sacks in
rathole. Used 50/50 pozmix cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Sherrill Compton (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God. ZENITH DRILLING CORP., INC.

(Signature) Sherrill Compton
Sherrill Compton
Suite 600, 200 W. Douglas, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of Sept., 1978

My commission expires 12/15/80

Sharon R. Allen
Sharon R. Allen Notary Public.

9-25-78
RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1978

CONSERVATION DIVISION
Wichita, Kansas

15-047-20394-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- HERRMANN #1
Located: W/2 SW SW, Section 32-24S-19W, Edwards County,
Kansas.

OWNER: Zenith Drilling Corporation, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 14, 1978
COMPLETED: June 19, 1978

TOTAL DEPTH: 3481'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 298	Sand, Clay and Blue Shale	Ran 7 joints new 23#, 8 5/8" casing, 282.73' set at 295' K.B. with 250 sacks 60/40 Pozmix with 3% cc. Plug down at 8:45 PM, 6-14-78, by Howco.
298 - 540	Shale	
540 - 1325	Shale and Red Bed	
1325 - 1341	Anhydrite	
1341 - 1350	Shale	
1350 - 2070	Shale and Lime Strs.	
2070 - 3481	Shale and Lime	Plugged.

9-25-78
RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1978
CONVENTED BY SCSJ
10/1/78