

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

10071-00-01  
API NUMBER 15-055-60002W

LEASE NAME Pleasant Praire

WELL NUMBER 49

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1650 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 32 TWP. 26 S RGE. 34 (E or W)

COUNTY Finney

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558 Garden City, KS 67846

PHONE#(316) 276-3693 OPERATORS LICENSE NO. 5293

Date Well Completed 4-4-60

Character of Well T.A'd WIW

Plugging Commenced 7-23-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-23-92

The plugging proposal was approved on 5-5-92 (date)

by Dodge City D.O. Steve Middleton Glen Barlow on location  
(KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? Previously mailed

Producing Formation Miss B Depth to Top 5092 Bottom 5100 P.B. T.D. 5171

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Miss B	Water	0	823	8-5/8	823	0
		0	5209	5 1/2	5209	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Pump 150 sks Class C w/ 3% CaCl2 & 100# hulls. Displace to 2000' w/ 48 bbls @ 280#. Let cmt set 4 hours. Tag cmt top w/ wire line @ 2649'. Perf 4 squeeze holes @ 810' in 5 1/2" csg. Break circulation down 5 1/2" csg & out 8-5/8 annulus and circ 167 sks 60/40 poz, 6% gel. Left csg & annulus full of cement.

(If additional description is necessary, use BACK of this form.)  
Cut off well head and resote location

Name of Plugging Contractor Dewell Schlumberger License No. \_\_\_\_\_

Address Ulysses, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

Ken Jehlik (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ken Jehlik 7-31-92

(Address) P.O. Box 558 Garden City, KS 67846

SUBSCRIBED AND SWORN TO before me this 30th day of \_\_\_\_\_, 1992

My Commission Expires: August 15, 1992

RECEIVED  
STATE CORPORATION COMMISSION  
Judith Richman  
Notary Public  
8-3-92  
CONSERVATION DIVISION  
Wichita, Kansas Form CP-  
Revised 05-C

B