


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.



Finney County. Sec. 21 Twp. 26 Rge. (E) 34 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Center NW NW SE
Lease Owner Magnolia Petroleum Company
Lease Name Earl Brown Unit "B" Well No. 1
Office Address Box #770, Great Bend, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Junked Hole
Date well completed August 26, 1949 19.
Application for plugging filed August 25, 1949 19.
Application for plugging approved 19.
Plugging commenced August 26, 1949 19.
Plugging completed August 26, 1949 19.
Reason for abandonment of well or producing formation Junked Hole

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dick Phillipy
Producing formation Depth to top Bottom Total Depth of Well 2740 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>None recorded</u>				<u>10-3/4</u>	<u>770</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Drill Pipe stuck on bottom; twisted off at 1810' from Kelly Bushing; cement/d hole at 1810' with 50 sacks cement; filled to bottom of surface casing with heavy mud; set plug in bottom of surface casing @ 760' and cemented with 15 sacks; filled to surface with heavy mud, set plug at 40' and cemented with 20 sacks.

RECEIVED
Cons. Division
AUG 31 1949 8-31-49
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to C. A. Hill, Superintendent, Magnolia Petroleum Co
Address Box #770, Great Bend, Kansas.

STATE OF Kansas COUNTY OF Barton, ss.
C. A. Hill (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box #770, Great Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of August 1949

My commission expires August 27, 1952 Notary Public.

PLUGGING
FILE SEC 21 T 26 R 34
BOOK PAGE 111 LINE 9

15-055-00736-0000

MAGNOLIA PETROLEUM COMPANY

Log of Well
Earl Brown Unit "B" Well #1
Center NW NW SE of Section 21-26S-34W
Finney County, Kansas.

Drilling Started - August 13, 1949
Drilling Completed - August 22, 1949
By: Keating Drilling Company
Tulsa, Oklahoma.

CASING RECORD:
10-3/4" Surface casing @ 770' w/400 sacks

FORMATION	TOP	BOTTOM
Sand & shells	0	130
Sand & gravel	130	200
Sand & shale	200	516
Shale	516	600
Blue shale	600	730
Red bed	730	770
10-3/4" Surface casing @ 770' w/400 sacks - circulated		
Red bed	770	775
Red bed & sand	775	1335
Sand & shale	1335	1835
Anhydrite	1835	1870
Shale & shells	1870	2035
Sandy shale	2035	2145
Anhydrite & shale	2145	2270
Shale & shells	2270	2330
Shale & gypsum	2330	2365
Sandy shale	2365	2420
Gypsum & shale	2420	2564
Gypsum	2564	2595
Lime & shale	2595	2675
Lime	2675	2740

Total Depth 2740' KB

Started out of hole with drill pipe to run Electric Log; drill pipe stuck and twisted off;

PLUGGING RECORD:

Cemented at top of drill pipe, 1810' w/50 sacks cement; filled hole with heavy mud to bottom of surface casing; set plug @ 760' and cemented with 15 sacks cement; filled with heavy mud to surface, set plug @ 40' and cemented with 20 sacks cement.

Plugging completed August 26, 1949.

RECEIVED

Conservation Div.

AUG 31 1949 8-31-49

STATE CORPORATION
COMMISSION
KANSAS

PLUGGING
FILE SEC 21-26S-34W
BOOK PAGE 111 LINE 9