

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
300 Colorado Derby Building  
Wichita, Kansas 67202

#1 WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-055-16016-000

LEASE NAME C. L. Reeve

WELL NUMBER 1

SPOT LOCATION C SW NE

SEC. 7 TWP. 26 RGE. 34 (EXX(W))

COUNTY Finney

Date Well Completed 6-6-59

Plugging Commenced 9-8-82

Plugging Completed 9-10-82

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Champlin Petroleum Company

ADDRESS 6441 N. W. Grand, Okla City, Ok 73116

PHONE # (405) 840-5521 OPERATORS LICENSE NO. 6417

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Minneola, Kansas

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing formation Morrow-Mississippi Depth to top 4860 bottom 4921 T.D. 5172

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4"	861'	None
				7"	5171'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Ran gauge ring and junk basket to 4838'. Ran 7" CIBP and set at 4800'. Set 2nd CIBP at fluid level at 1146'. Mix and pump 150 sx Litewate cement in 7" casing. Filled 7" casing from 1146' to surface. Mix and pump 25 sx Litewate cement in 7" and 10 3/4" annulus and pressured to 700#. Cut off casing and welded on plate. Well is P & A.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rosel Perforators License No.                       
Address Box 1136, Liberal, Kansas 67901

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

SEP 25 1984

Marilyn Day (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) Marilyn Day  
(Address) 6441 N.W. Grand, Okla City, Ok 73116

SUBSCRIBED AND SWORN TO before me this 19th day of September, 19 84

Notary Public

My Commission expires: 10-8-87