


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 3 Twp. 24S Rge. (E) 23 (W)
Location as "NE/CNWxSWx" or footage from lines C SE SW
Lease Owner Rains & Williamson Oil Co.
Lease Name Schaffer Well No. 1
Office Address 1425 Wichita Plaza Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 4, 19 64
Application for plugging filed January 4, 19 64
Application for plugging approved January 4, 19 64
Plugging commenced January 4, 19 64
Plugging completed January 4, 19 64
Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Sublette, Kansas
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4845 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	249'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 25 sacks cement at 700'. Filled hole with rotary mud to 250'. Spotted with 25 more sacks cement. Filled hole with rotary mud to 40' of base of cellar. Set plug and hulls and capped with 15 sacks cement. Plugging completed at 12:30 P.M. 1-4-64.

RECEIVED
STATE CORPORATION COMMISSION

JAN 8 1964

1-8-64

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Wilson Rains (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains
1425 Wichita Plaza Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of January, 1964.

My commission expires August 14, 1966

Sandra Ames
Sandra Ames Notary Public.

ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co.
and Phillips Petroleum Company
No. 1 SCHAFER
C SE SW Sec. 3-248-23W
Hodgeman County, Kansas

CONTRACTOR: Rains & Williamson
Oil Co.
COMM. 12-21-63
COMP. 1-4-64

Remarks: Set 3-5/8" surface
casing at 249' with
140 sacks cement.

Formations:

Surface Clay	40'
Clay	55'
Sand	70'
Shale & Shells	105'
Shale	365'
Sand	730'
Shale & Red Bed	1015'
Anhydrite	1021'
Shale	1110'
Dakota Sand	1245'
Shale	1260'
Shale & Red Bed	1618'
Anhydrite	1845'
Shale & Shells	2350'
Lime & Shale	3135'
Shale & Lime	3930'
Lime & Shale	4450'
Lime	4675'
Lime & Shale	4735'
Lime	4845'
Rotary Total Depth (D&A)	4845'

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1964

CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is
true and correct to the best
of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains
Partner

Subscribed and sworn to before me, a Notary Public in and for the
State of Kansas, County of Sedgwick, this 7th day of January, 1964.

My Commission Expires: August 14, 1966

Sandra Ames
Sandra Ames, Notary Public