

15-083-20957-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

RECEIVED Form CP-4  
STATE CORPORATION COMMISSION Rev. 12-15-80

FEB 25 1982

2-25-82

CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Hodgeman SEC. 9 TWP. 24S RGE. 23 E/W  
Location as in quarters or footage from lines:  
Center of NE/4 of NW/4

	⊙		

Lease Owner Tuthill & Barbee  
Lease Name Schaffer Well No. 1-9  
Office Address 300 Fisk Bldg. Amarillo, Texas 79101  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 2-22-82  
Plugging completed 2-22-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Dry Hole  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
Producing formation Mississippi Depth to top 4738 bottom 4780 T.D. 4810  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Mississippi</u>	<u>Water</u>	<u>4738</u>	<u>4780</u>	<u>8 5/8"</u>	<u>760</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

70 sacks cement @ 1020'  
40 sacks cement @ 720'  
Rubber plug @ 40' with 1 sack of hulls, 10 sacks of cement to surface.  
5 sacks cement in rat hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_

STATE OF TEXAS COUNTY OF POTTER, ss.

Dan E. Steed (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Dan E. Steed  
300 Fisk Bldg. Amarillo, TX 79101  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 19 82

My Commission expires: 3/13/85

Cheryl Flury  
Notary Public.

DRILLERS LOGSCHAFFER NO. 1-9

CASING RECORD:	OPERATOR: Tuthill & Barbee, Inc.	DESCRIPTION:
8-5/8" set @ 760' w/425 sax cement	CONTRACTOR: Sage Drilling Co., Inc.	NE NW Section 9-24S-23W Hodgeman County, Kansas
TOTAL DEPTH: 4810'	COMMENCED: February 14, 1982	
	COMPLETED: February 21, 1982	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed	0	45	
Shale & Clay	45	392	
Shale	392	761	
Red Bed	761	2003	
Anhydrite	2003	2803	
Shale	2803	3215	
Shale & Sand	3215	3441	
Shale	3441	3850	
Shale & Sand	3850	4070	
Shale	4070	4380	
Shale & Lime	4380	4617	
Lime & Shale	4617	4696	
Shale & Lime	4696	4755	
Lime	4755	4810	Logged Hole, Ran DST #1 D & A

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.


SAGE DRILLING CO., INC.

BY John R. Bartholomew  
John R. Bartholomew

3-12-82  
Subscribed and sworn to before me this 24th day of February, 1982.

RECEIVED  
STATE PROBATION COMMISSION

Louise K. Whitted  
Louise K. Whitted, Notary Public



MAR 12 1982  
CONSERVATION DIVISION  
Wichita Kansas