

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 12 Twp. 24S Rge. 23 (W)

Location as "NE/CNW/SW" or footage from lines C NW NW

Lease Owner Jones-Gebert Oil, Inc.

Lease Name Herrman Well No. 1

Office Address 205 Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Jan. 12 19 64

Application for plugging filed Jan. 12 19 64

Application for plugging approved Jan. 12 19 64

Plugging commenced Jans. 12 19 64

Plugging completed Jan. 12 19 64

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott

Producing formation Depth to top Bottom Total Depth of Well 4811' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	268'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bottom plug @650' w/25 sx. mud, set plug @300' w/25 sx. mud, set top plug @40' w/10 sx. mud.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 20 1964  
1-20-64  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jones-Gebert Oil, Inc.  
Address 205 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. George R. Jones (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *George R. Jones*  
205 Central Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16th day of January, 19 64

My commission expires February 1, 1964  
Barbara J. Layton Notary Public.

DRILLERS' LOG


Company: Jones-Gebert Oil, Inc.  
 Contractor: Jones-Gebert Oil, Inc.  
 Farm: #1 Herrman, C NW NW  
 Sec. 12-24S-23W,  
 Hodgeman Co., Kansas  
 Commenced: 12/16/63  
 Completed: 1/12/64  
 Casing: 268' of 8-5/8" w/200 sx.

0	-	268	Surface hole
268	-	960	Surface clay & shale
960	-	1090	Blaine sand
1090	-	1335	Shale & shells
1335	-	1385	Shale & shells
1385	-	1420	Anhydrite ?
1420	-	1885	Shale & shells
1885	-	2180	Shale & lime shells
2180	-	2230	Shale & shells
2230	-	2430	Brown lime
2430	-	2590	Shale & lime
2590	-	2750	Lime
2750	-	2850	Lime
2850	-	2985	Lime & shale
2985	-	3100	Lime
3100	-	3240	Lime & chalk streaks
3240	-	3460	Lime & chalk streaks
3460	-	3570	Shale & lime
3570	-	3708	Shale & lime
3708	-	3860	Shale & lime
3860	-	3895	Lime & shale
3895	-		Fishing
3620	-	3640	Lime
3640	-	3650	Shale & lime
3650	-	3700	Shale & lime
3700	-	3740	Lime & shale
3740	-	3860	Lime & shale
3860	-	3975	Lime & shale
3975	-	4052	Lime
4052	-	4130	Lime w/chalk streaks
4130	-	4170	Lime
4170	-	4192	Lime
4192	-	4248	Lime
4248	-	4300	Lime
4300	-	4343	Lime
4343	-	4375	Lime
4375	-	4425	Lime
4425	-	4441	Lime
4441	-	4500	Lime
4500	-	4560	Lime
4560	-	4605	Lime
4605	-	4616	Lime
4616	-	4625	Lime
4625	-	4635	Lime
4635	-	4690	Miss.
4690	-	4733	Lime
4733	-	4795	Lime
4795	-	4816	Log T. D.
		4811	Drillers' Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 20 1964  
 1-20-64  
 CONSERVATION DIVISION  
 Wichita, Kansas


I, George R. Jones, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Herrman, C NW NW, Sec. 12-24S-23W, Hodgeman County, Kansas, as reflected by the files of Jones-Gebert Oil, Inc.

  
\_\_\_\_\_  
GEORGE R. JONES

State of Kansas        )  
                              ) ss:  
County of Sedgwick )

Subscribed and sworn to before me, a Notary Public , in and for Sedgwick County, Kansas, this 16th day of January, 1964.

My Commission Expires:  
February 1, 1964

  
\_\_\_\_\_  
Barbara J. Layton, Notary Public