


STATE OF KANSAS  
STATE CORPORATION COMMISSION

## WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plat

Hodgeman County. Sec. 11 Twp. 24 Rge. 23 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NE SE

Lease Owner Zenith Drilling Corporation, Inc.  
Lease Name Meyer Well No. 1  
Office Address 200 W. Douglas, Suite 600, Wichita 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed 5/10/79 19  
Application for plugging filed 5/10/79 19  
Application for plugging approved 5/10/79 19  
Plugging commenced 5/10/79 19  
Plugging completed 5/10/79 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation Depth to top Bottom Total Depth of Well  
Show depth and thickness of all water, oil and gas formations. TD 4675'

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	331	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

1st plug @ 900' with 50 sacks 50/50 Poz, 6% gel

2nd plug @ 350' with 35 sacks 50/50 Poz, 6% gel

Top plug at 40' with 10 sacks 50/50 Poz, 6% gel

5 sacks in rathole

Job complete at 8 a.m. 5/10/79

5-18-79  
RECEIVED  
STATE CORPORATION COMMISSION

MAY 18 1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

James C. Remsberg of Slawson Drilling Co., Inc. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature)


James C. Remsberg  
200 Douglas Building, Wichita 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of May, 1979

Mary Lou Taylor

Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



DRILLERS LOG

OPERATOR: Zenith Drilling Corporation, Inc.  
200 West Douglas, Suite 600  
Wichita, Kansas 67202

LEASE: Meyer No. 1  
NE SE Sec. 11-24S-23W  
Hodgeman County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
200 Douglas Building  
Wichita, Kansas 67202

COMMENCED: 5/1/79

COMPLETED: 5/10/79

RTD: 4675'

SURFACE CASING: 8-5/8" set at 331' with 225 sacks cement

0' to 335' 12 1/2" Surface Hole  
335' to 1176' Shale & Shells  
1176' to 1460' Shale & Sand  
1460' to 1488' Anhydrite  
1488' to 2866' Shale & Lime  
2866' to 3900' Lime & Shale  
3900' to 4011' Limestone  
4011' to 4170' Lime & Shale  
4170' to 4294' Lime  
4294' to 4400' Lime stone  
4400' to 4572' Lime  
4572' to 4636' Limestone  
4636' to 4675' Lime  
RTD 4675'

5-18-79  
RECEIVED  
STATE CORPORATION COMMISSION  
MAY 18 1979  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.  
hereby state the above is an accurate copy of the log for the Zenith Drilling  
Corporation, Inc. Meyer No.1

*James C. Remsberg*  
James C. Remsberg

Subscribed and sworn to me this  
15th day of May, 1979

*Mary Lou Taylor*  
Mary Lou Taylor, Notary

My commission expires January 17, 1981

